

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Project Engineer (E&M), Rohini OCP, NK Area, CCL

Name of the Work / Contract No:	Rearrangement of 3.3kV OH line to Rohini colony for erection of cradle guards for safe of road crossing at different locations, under Rohini OCP, NK Area.	NIT No: PE(EnM)/RH/eNIT/2024-25/09; Dated:12.11.2024			
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Erection of steel tubular or rail pole strut in cement concrete 1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required. Above 10.00 meters and up to 11.00 meter.	7	Nos		0.00	INR Zero Only
2	Dismantling of pole/ street light standard/ strut embedded in cement concrete foundation etc. as required	7	Nos		0.00	INR Zero Only
3	Dismantling of overhead lines comprising of copper/ aluminum overhead conductor, G.I. wire, cross arms, insulators etc. as required.	147	kg		0.00	INR Zero Only
4	Supplying and erection of galvanized stay set complete with 19/ 20 mm dia. X 1.8 meters long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm thick, thimble, stay clamps, turn buckle (20 mm X 60 mm), 7/ 4.00 mm dia. G.I. stay wire and 11 KV strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size) foundation including excavation and refilling etc. as required.	4	Nos		0.00	INR Zero Only

5	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per meter) cross arm 6mm angle iron bracket welded to the channel iron and complete with 50 mm X 6 mm M.S. flats iron clamps, bolts and nuts, including drilling holes for insulator pins/ fittings, bolts, nuts and washers etc (as per drawing) and painting with primer and finish paint as required.	6	Nos		0.00	INR Zero Only
6	Erection of double pole 3 wire cross arm for 11KV/22KV/33KV overhead lines as required.	6	Nos		0.00	INR Zero Only
7	Supplying and erection of 11kV disc insulator for 11kV overhead lines with galvanised insulator fittings, ball and socket type and complete with galvanised strain clamps, bolts, nuts, washers etc. as required.	12	Set		0.00	INR Zero Only
8	Supplying and erection of 11kV pin insulator complete with large steel head G.I. pin, nuts, washers etc. as required.	12	Set		0.00	INR Zero Only
9	Erection of disc/pin insulator for 11kV over head lines as required.	12	Set		0.00	INR Zero Only
10	Erection of all aluminium conductor of 7/3.40 mm to 7/4.00 diameter and above including binding etc. as required	150	kg		0.00	INR Zero Only
11	Erection of cradle guard as required.	100	Nos		0.00	INR Zero Only
12	Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc. with charcoal/ coke and salt as required.	5	Nos		0.00	INR Zero Only
13	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				