

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Project Engineer (E&M), Rohini OCP, NK Area, CCL

Name of the Work / Contract No:	Installation of lightning arrester, GOAB, Earth pit along with accessories in 11kV Overhead line at Main Sub- station (2X3MVA) and dismantling / erection of overhead line at Weighbridge No. - 01, under Rohini OCP, NK Area	NIT No: PE(EnM)/RH/eNIT/2024-25/08; Dated:12.11.2024
---------------------------------	---	--

	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)			
--	---	---	--	--	--

ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Erection of steel tubular or rail pole strut in cement concrete 1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required. Above 10.00 meters and up to 12.00 meter.	4	Nos		0.00	INR Zero Only
2	Supplying and erection of galvanized stay set for 11 KV overhead lines complete with 19/ 20 mm dia. X 1.8 meters long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm thick, thimble, stay clamps, turn buckle (20 mm X 60 mm), 7/ 4.00 mm dia. G.I. stay wire and 11 KV strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size) foundation including excavation and refilling etc. as required.	4	Nos		0.00	INR Zero Only

3	Supplying of two lengths of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per meter) double pole cross arm for 2/4 wire 11KV overhead line conductors complete with through bolts and nuts for clamping to the poles, 50 mm X 6 mm M.S. flats welded on one side to the channel iron and with bolts and nuts on the other side for tying the cross arms together, including drilling holes for insulator pins/ fittings, bolts, nuts and washers etc (as per drawing) and painting with primer and finish paint as required.	2	Nos		0.00	INR Zero Only
4	Erection of double pole 3 wire cross arm for 11KV overhead lines as required.	2	Nos		0.00	INR Zero Only
5	Supplying and making outdoor cable end termination with heat shrinkable jointing kit complete with all accessories including lugs suitable for following size of 3 core, XLPE aluminum/ copper conductor cable of 11 KV grade as required 120 sq. mm	2	Set		0.00	INR Zero Only
6	Supplying and erection of three piece nonlinear resistor type lightning arrester suitable for 3 wire, 11 KV overhead lines with rated voltage 9 KV (rms) with a nominal discharge current rating of 5 KA and complete with galvanized clamping arrangement, G.I. bolts, nuts, washers etc. as required.	3	Set		0.00	INR Zero Only
7	Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc. with charcoal/ coke and salt as required.	6	Set		0.00	INR Zero Only
8	Supplying, installing, testing and commissioning of following capacity TPN tap off box made of 1.6mm thick sheet steel enclosure duly painted with powder coating on existing rising mains complete with TPN disconnecter FSU and HRC fuses, connections, earthing etc. as required.100 A TPN	1	Nos		0.00	INR Zero Only
9	Providing and fixing 50mm X 6mm G.I strip on surface or in recess for loop earthing as required.	45	Meter		0.00	INR Zero Only
10	Erection of ACSR conductor of 7/3.35 mm to 7/4.00 diameter and above including binding etc. as required	60.66	Kg		0.00	INR Zero Only
11	Providing of 35 Sq.mm 3.5core Aluminum Armored cables.	45	Meter		0.00	INR Zero Only
12	Dismantling of 11kv, GOAB isolator at double pole structure in overhead line feeder.	2	Set		0.00	INR Zero Only
13	Providing of 11kv, 400Amp. GOAB Isolator.	2	Set		0.00	INR Zero Only
14	Providing of Horn gape fuse unit.	2	Set		0.00	INR Zero Only
15	Erection of 11kv, 400Amp GOAB isolator at double pole structure in overhead line feeder.	2	Set		0.00	INR Zero Only
16	Dismantling of pole/ street light standard/ strut embedded in cement concrete foundation etc. as required	4	Nos		0.00	INR Zero Only
17	Dismantling of overhead lines comprising of copper/ aluminum overhead conductor, G.I. wire, cross arms, insulators etc. as required.	80	Kg		0.00	INR Zero Only
18	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only

Quoted Rate in Words

INR Zero Only