

Tender Inviting Authority: Project Engineer(EnM),Tarmi OCP										
Name of the Work / Contract No:	Electrical wiring as well as complete lighting arrangement for safety purpose of Karipani Durga Mandap, Tarmi Durga Mandap and Tarmi Kali Mandir in respect of Tarmi OCP."					NIT No. : TOCP/PE(EnM)/e.NIT/24-25/07 dt.16.11.2024				
Category of Services (To Be Selected by Department)					Category of Bidder (To Be Selected)	To Be Entered by Department				
ITC Not Available	Works Contract				Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :					Select	18	0.00	0.00	0.00	
<b>PRICE SCHEDULE</b>										
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )										
NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER	NUMBER #	NUMBER #	NUMBER #	TEXT #		
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder In Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words			
1	2	3	4	5	6	7	8			
1.01	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface/ recessed medium class PVC conduit, with piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required: Group A. a) Bulb Point-62 b) Fan Point-10 c) Tubelight Point-12 d) Exhaust Point-09	93	Nos			0.00	INR Zero Only			
1.02	Supplying and fixing metal box of 180 mm x 100 mm x 60 mm deep (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 6 pin 5/6 & 15/16 amps socket outlet and 15/16 amps piano type switch, connection, painting etc. as required.	50	Nos			0.00	INR Zero Only			
1.03	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/isolator). : 2+2 way, SPN, single door, MCB DB.	8	Nos			0.00	INR Zero Only			
1.04	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole & neutral.	8	Nos			0.00	INR Zero Only			
1.05	Supplying and fixing stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate as required.	16	Nos			0.00	INR Zero Only			
1.06	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required.	3	Set			0.00	INR Zero Only			
1.07	Providing and fixing following capacity TP&N disconnector fuse switch unit inside the existing panel board with ISI marked HRC fuses including drilling holes in cubicle panel, making connections, etc. as required.	3	Nos			0.00	INR Zero Only			
1.08	Providing and fixing 50mm dia x 3.2 metres G.I. pipe (including accessories) complete with 50mm x 50mm x 6mm angle iron bracket on wall and 75mm x 90mm shackle insulator with straps for house service connection including painting the angle and flat iron with primer and finish paint etc. as required	3	Nos			0.00	INR Zero Only			
1.09	G.I. wire 8 SWG (+) Erection of 8 SWG GI wire.	18	Kg			0.00	INR Zero Only			
1.1	Supplying and drawing following sizes FRLS PVC insulated copper conductor, single core cable in existing surface/ recessed steel/ PVC conduit as required. : 2 x 2.5 sq.mm.	160	Mtr			0.00	INR Zero Only			
1.11	Supplying and drawing following sizes FRLS PVC insulated copper conductor, single core cable in existing surface/ recessed steel/ PVC conduit as required. : 2 x 4 sq.mm.	115	Mtr			0.00	INR Zero Only			
1.12	Supply & fixing of LED panel light for ceiling in Karipani Durga Mandap 12 watts 240 volt of reputed make.	30	Nos			0.00	INR Zero Only			
1.13	Supply & fixing of LED bulb 12 watt 240 volt of reputed make.	18	Nos			0.00	INR Zero Only			
1.14	Supply & fixing of LED tube 20 watt 240 volt of reputed make.	10	Nos			0.00	INR Zero Only			
1.15	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos			0.00	0.00	INR Zero Only		
<b>Total in Figures</b>							<b>0.00</b>	INR Zero Only		
<b>Quoted Rate in Words</b>					<b>INR Zero Only</b>					