

Item Rate BoQ

Tender Inviting Authority:	Dy. Manager (E&M)/Kedla Washery.
Name of the Work / Contract No:	Different off-loading mechanical works pump section of main plant at Kedla Washery. NIT No-PO/KWE-Tender/24-25/ 66 date:-16.11.2024

Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department				
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :	Select	18	0.00	0.00	0.00	0.00

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes In Rs. P	TOTAL AMOUNT In Words
1	1.Repairing of damaged rake-arms of static thickener. (a) Dismantling of scraper.	0.929	MT			0.00	INR Zero Only
2	Shifting of scraper for repairing and shifting of after repairin g.	1.858	MT			0.00	INR Zero Only
3	Installation after repairing.	0.929	MT			0.00	INR Zero Only
4	Alignment of rake arm after repairing. Labour cost.	4.000	Shift			0.00	INR Zero Only
5	Thickener by-pass arrangement for plant operation. Labour cost.	3.000	Shift			0.00	INR Zero Only
6	Fasteners used for repairing of rake-arm. (a) H.T. Bolt (M24x120)mm	30.000	Nos.			0.00	INR Zero Only
7	(b) H.T. Bolt (M20x65)mm	150.000	Nos.			0.00	INR Zero Only
8	(c) H.T. Bolt (M16x50)mm	175.000	Nos.			0.00	INR Zero Only
9	Dismantling , repairing and re-installation of Hyd. Jack of static thickener, Wt. of Hyd. Jack=1.1MT & break down of gear box of static thickener. Wt. of gear box to be dismantling.=2MT .Hyd. Jack+Gear box= 1.1+2= 3.1MT (a) Dismantling of equipments.	3.100	MT			0.00	INR Zero Only
10	(b) Shifting of equipments for repairing and Shifting after repairing.	6.200	MT			0.00	INR Zero Only
11	(c) Installation of equipments for operation.	3.100	MT			0.00	INR Zero Only
12	Fabrication and erection of over-head structure of 258 and 260 pump removing. (a) Shifting of materials for fabrication.	1.071	MT			0.00	INR Zero Only
13	(b) Installation after fabrication.	1.071	MT			0.00	INR Zero Only
14	Collection of m.S. plate of dia 500mm and length 40m, after dismantling from side washery to Kedla washery. Dismantling of pipe of dia 500mm and length 40mtrs. Wt. of pipe =3.14X0.500X40mX8mmX7.85Kg/mm mtr. ² =3943.84Kg (a) Dismantling of pipe.	3.943	MT			0.00	INR Zero Only
15	(b) Shifting of pipe.	3.943	No.			0.00	INR Zero Only
16	Dismantling, Shifting for repairing, shifting after repairing for Installation of following break down. (a) Dismantling of pump for repairing.	10.920	MT			0.00	INR Zero Only
17	(b) Shifting of pump for repairing and Shifting of pump after repairing.	21.840	MT			0.00	INR Zero Only
18	(c) Installation of pump after repairing.	10.920	MT			0.00	INR Zero Only
19	(d) Dismantling of motor after repairing of base	8.410	MT			0.00	INR Zero Only
20	€ Installation of motor after repairing of base as well as alignment of pump	8.410	MT			0.00	INR Zero Only
21	Replacement of damaged pipe line of 270 suction pipe and 270/C delivery pipe line. (a) Dismantling of pipe.	0.926	MT			0.00	INR Zero Only
22	(b) Shifting of pipe for repairing and Shifting of pipe after repairing.	1.852	MT			0.00	INR Zero Only
23	(c) Installation of pipe for operation.	0.926	MT			0.00	INR Zero Only
24	Total Impact of GST for the purpose of CTC	1.00	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only						