

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority: Staff Officer Civil Piparwar Area.

Name of Work : Repair of drain and boundary wall at 1BR colony under GM Unit, Piparwar Area.

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	t	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1.01	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30cm in depth, 1.5m in width as well as 10sqm on plan) including getting out and disposal of excavated earth lead upto 50m and for all lift, as directed by Engineer-in-charge. All kinds of soil	51.390	Cum	128.05	6580.49	INR Six Thousand Five Hundred & Eighty and Paise Forty Nine Only
1.02	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	127.500	sqm	32.00	4080.00	INR Four Thousand & Eighty Only
1.03	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 5.0 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	8.437	Cum	5322.15	44902.98	INR Forty Four Thousand Nine Hundred & Two and Paise Ninety Eight Only
1.04	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level upto floor level in all shapes and sizes in : Cement mortar 1:6 (1 cement: 6 coarse sand)	9.000	Cum	6494.75	58452.75	INR Fifty Eight Thousand Four Hundred & Fifty Two and Paise Seventy Five Only
1.05	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	96.000	sqm	217.70	20899.20	INR Twenty Thousand Eight Hundred & Ninety Nine and Paise Twenty Only
1.06	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand)	127.500	sqm	284.75	36305.63	INR Thirty Six Thousand Three Hundred & Five and Paise Sixty Two Only

1.07	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	5.310	Cum	1844.00	9791.64	INR Nine Thousand Seven Hundred & Ninety One and Paise Sixty Four Only
1.08	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement:4 coarse sand (zone-III) derived from natural sources:8 graded stone aggregate 40 mm nominal size derived from natural sources)	9.495	Cum	5167.75	49067.79	INR Forty Nine Thousand & Sixty Seven and Paise Seventy Nine Only
1.09	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement:1.5 coarses and (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	18.390	Cum	7365.50	135451.55	INR One Lakh Thirty Five Thousand Four Hundred & Fifty One and Paise Fifty Five Only
1.10	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	1287.300	Kg	75.85	97641.71	INR Ninety Seven Thousand Six Hundred & Forty One and Paise Seventy Only
1.11	Centering and shuttering including strutting, propping etc. and removal of form work for: Foundations, footings, bases for columns	179.400	sqm	262.55	47101.47	INR Forty Seven Thousand One Hundred & One and Paise Forty Seven Only
1.12	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50m and for all lift	17.130	Cum	114.40	1959.67	INR One Thousand Nine Hundred & Fifty Nine and Paise Sixty Seven Only
1.13	Carriage of material mechanical transpor including loading unloading and stacking earth upto 5 KM	50.000	Cum	210.10	10505.00	INR Ten Thousand Five Hundred & Five Only
1.14	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					522739.86	INR Five Lakh Twenty Two Thousand Seven Hundred & Thirty Nine and Paise Eighty Six Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only					