

Validate

Print

Help

**Item Rate BoQ**

Tender Inviting Authority: Staff Officer Civil Piparwar Area.

Name of the Work : Repair of CTR near CISF checkpoint under CHP CPP, Piparwar Area.

	Category of Services (To Be Selected by Department)	Category of Bidder (To Be)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

**PRICE SCHEDULE**

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.01	Demolishing cement concrete manually/ by mechanical means including disposal of material with in 50 metres lead as per direction of Engineer- in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	351.00	cum			0.00	INR Zero Only
1.02	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth,1.5min width as well as10 s qm on plan) including getting out and disposal of excavated earth lead upto 50 mand for a Illift ,as directedby Engineer-in- charge. All kinds of soil	203.43	cum			0.00	INR Zero Only
1.03	Granular Sub base with close Graded Material Table :400-1) Plant Mix Method (Construction of granular sub- base by providing clouse graded Material, mixing in a meachanical mix plant OMC, Carriage of mixed Material to work site, spreading in uniform layers with motor grader on preparation surface and compacting with vibratory power roller to achieve the desired density, complete as per clasue :401) for grading -II Material.	117.00	cum			0.00	INR Zero Only
1.04	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1Cement :3 coarses and (zone-III) derived from natural sources : 6 graded stone aggregate 40 mm nominal size derived from natural sources)	117.00	cum			0.00	INR Zero Only

1.05	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:1½:3 (1 Cement : 1½ coarse sand (zone-II) derived from natural sources.3 graded stone aggregate 20 mm nominal size derived from natural sources)	351.00	cum			0.00	INR Zero Only
1.06	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete.	72.00	sqm			0.00	INR Zero Only
1.07	Filling available excavated earth (excluding rock) in trenches, plinth Sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50m and for all lift	36.00	cum			0.00	INR Zero Only
1.08	Carriage of material by mechanical transporting including loading, unloading and stacking earth upto 05 KM Lead.	203.43	cum			0.00	INR Zero Only
1.09	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos		0.00	0.00	INR Zero Only
<b>Total in Figures</b>						<b>0.00</b>	INR Zero Only
<b>Quoted Rate in Words</b>	<b>INR Zero Only</b>						