

[Validate](#)[Print](#)[Help](#)**Item Rate BoQ**

Tender Inviting Authority: Staff officer (E&M), Amrapali- Chandragupta Area, CCL						
Name of the Work / Contract No:	Installation of 03 nos. of Diesel Engine 1000 GPM pump in different places of mines arrangement of connection with pipelines of 6" dia and 4" dia pipeline (300 Mtr. Each Approx.) for supply water in OB dump Miyawaki tree plantation in 4 hectare area (approx) at Amrapali OCP under A-C Area			NIT No: G.M.(A-C)/S.O.(E&M)/e-NIT/24-25/30; Dated: 18.11.2024		
	Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract		Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :			Select	0.00	0.00	0.00
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Welding by gas or electric plant including transportation of plant at site etc. as complete	14200.000	CM		0.00	INR Zero Only
2	arraiage of 150mm dia lead 5 Kms R.C.C. pipe, A.C. pipes, steel cylinder, R.C. pipes, S.C.I. pipes, C.I. Pipes and unreinforces cement pipes for 300 Mtr. Length	300.000	Mtr.		0.00	INR Zero Only
3	Laying in position centrifugally cast (Spun) iron S&S or flanged pipes (excluding cost of pipe). (300 Mtr X 12.91 Kg/m = 38.73 Quintal) (300 Mtr X 28.26Kg/m= 84.78 Quintal). Total- 124.00	124.00	Quintal		0.00	INR Zero Only
4	Earth work in excavation by mechanical means (Hydraulic excavator)/ Manual meand in foundation trenches or drains (not exceeding 1.5 m in width or 10 sq.mm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5m, including gettng out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m. (All Kind of soil). (Laying = 300 X 0.5 X 0.3= 45 CuM, Dismantaling= 300 X 0.3 X 0.8 = 72 CuM. Total (117 CuM)	117.00	CuM		0.00	INR Zero Only
5	Providing flanged joints to double flanged C.I./D.I. pipes and specials, including testing of joints. 150 mm dia. pipe	21.00	Nos.		0.00	INR Zero Only

6	Providing, laying, testing & Comissioning of 'B' class medium duty G.I. pipe conforming to IS11239 including welding, fitting like elbows, tees, flanges, tapers, nuts, gaskets etc. and fixing the pipe on the wall/ ceiling with suitable clamps/ support frame and painting with two or more coats o synthetic enamel paint of required shade complete as required. 25 mm	16.00	Mtr.		0.00	INR Zero Only
7	BUTTER FLY VALVE (MANUAL) with Ci body SS Disc, Nitrile Rubber seal & O- Ring PN- 16 Pressure rating for chilled water/ hot water circulation as sepcified. 50 mm dia.	8.00	Nos.		0.00	INR Zero Only
8	Carriage of 100 mm dia lead 5 Kms R.C.C. pipe, A.C. pipes, steel cylinder, R.C. pipes, S.C.I. pipes, C.I. Pipes and unreinforces cement pipes for 300 Mtr. Length	300.00	Mtr.		0.00	INR Zero Only
9	NON- RETURN VALVE with dual plate of CI body SS plates vulcanized NBR seal flanged end & PN 16 Pressure rating as specified.	3.00	Each		0.00	INR Zero Only
10	Providing and fixing of C.I. Slucie Valves (with Cap) complete with bolts, nuts, rubber inseration etc. (the tail pieces if required will be paid separately): 150 mm dia.	4.00	Nos.		0.00	INR Zero Only
11	Providing and fixing foot valves (with cap) complete as specified for 150mm dia suction Pipe	3.00	Nos.		0.00	INR Zero Only
12	Shifiting & installation of 1000 GPM Pump	3.00	Nos.		0.00	INR Zero Only
27	BUTTER FLY VALVE (MANUAL) with Ci body SS Disc, Nitrile Rubber seal & O- Ring PN- 16 Pressure rating for chilled water/ hot water circulation as sepcified. 100 mm dia.	1.00	Nos.		0.00	INR Zero Only
28	Total impact of GST for the purpose of CTC	1.000	Job	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				