

Validate

Print

Help

**Percentage BoQ**

Tender Inviting Authority: Staff Officer(Civil), Kuju Area

Name of Work : Providing retaining wall for embankment protection along CTR at Topa OCP under Kuju Area.

	<b>Category of Services (To Be Selected by Department)</b>	<b>Category of Bidder( To Be Selected by Bidder)</b>	<b>To Be Entered by Department</b>		
<b>ITC Not Available</b>	<b>Works Contract</b>	<b>Bidder's Status (Mandatory)</b>	<b>Rate of GST (in %)</b>	<b>GST to be Paid By Bidder (in Rs.)</b>	<b>GST to be Paid By CIL/Subsidiary (in Rs.)</b>
<b>Name of the Bidder/ Bidding Firm / Company :</b>		<b>Select</b>	<b>18.00</b>	<b>0.00</b>	<b>0.00</b>

**PRICE SCHEDULE**

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
0	<b>Item Description/ Heading</b>					
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. Ordinary rock, Depth up to 3m, Mechanical Means.	450.00	Cum	62.00	<b>27900.00</b>	INR Twenty Seven Thousand Nine Hundred Only
2	Plain/Reinforced Cement Concrete in Open Foundation complete as per Drawing and Technical Specifications. PCC Grade M15	45.00	Cum	7010.00	<b>315450.00</b>	INR Three Lakh Fifteen Thousand Four Hundred & Fifty Only
3	Plain/Reinforced Cement Concrete in Open Foundation complete as per Drawing and Technical Specifications. RCC Grade M25 , Using Batching Plant, Transit Mixer and Concrete Pump	198.75	Cum	7056.00	<b>1402380.00</b>	INR Fourteen Lakh Two Thousand Three Hundred & Eighty Only
4	Supplying, Fitting and Placing un-coated HYSD bar Reinforcement in Foundation complete as per Drawing and Technical Specifications.	15.90	mt	108448.00	<b>1724323.20</b>	INR Seventeen Lakh Twenty Four Thousand Three Hundred & Twenty Three and Paise Twenty Only
5	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications	200.00	nos	143.00	<b>28600.00</b>	INR Twenty Eight Thousand Six Hundred Only

6	Construction of Embankment with Material Deposited from Roadway Cutting (Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of table 300-2) Rolling with vibratory roller 3.17(j)	7500.00	Cum	78.00	585000.00	INR Five Lakh Eighty Five Thousand Only
7	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos	0.00	0.00	INR Zero Only
<b>Total in Figures</b>					<b>4083653.20</b>	INR Forty Lakh Eighty Three Thousand Six Hundred & Fifty Three and Paise Twenty Only
<b>Quoted Rate in Figures</b>			Select		0.00	INR Zero Only
<b>Quoted Rate in Words</b>	<b>INR Zero Only</b>					