Item Rate BoQ

Validate Print Help

Tender Inviti	Tender Inviting Authority: PROJECT OFFICER, RRS, DAKRA, NK AREA, CCL								
Work /	Repairing, installation, making & connections of lights including required electrical wiring at six nos. EOT crane shops and laying & making connections through OHL to main switches with installation of earth pits and jointing kit with required accessories at Regional Repair Shop (NK) Dakra under GM Unit, NK Area.		NIT No: PO/RRS/NK/e-NIT/2024-25/15		Dt. 13/01/2025				
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)							
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)				
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00				

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the
Bidder Name and Values only)

Bidder Name and Values only)									
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #			
SL No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words			
1	2	3	4	6	7	8			
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium cass PVC conduit, with piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required.	45	Nos.		0.00	INR Zero Only			
2	Supplying and fixing metal box of 180mm X 100mm X 60mm deep(nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 6 pin 5/6 & 15/16 amps socket outlet and 15/16 amps plano type switch, connection, painting etc. as required.	10	Nos.		0.00	INR Zero Only			
3	Supplying and fixing of DP sheet steel enclosure on surface/ recess along with 32 amps, 240Volts "C" curve DP MCB complete with connections, testing and commissioning etc. as required.	6	Nos.		0.00	INR Zero Only			
4	Supplying and fixing of 32 mm dia. X 2.00 meters long G.L. pipe (medium class) bracket for mounting of fluorescent / HPMV / HPSV street light fitting on pole including bending the pipe to the required shape, 2 nos. 40 mm X 3 mm flat iron clamps with nuts, bolts and washer, painting the flat iron with primer and finish paint etc. as required.	45	Nos.		0.00	INR Zero Only			
5	Supplying and making outdoor cable end termination with heat shrinkable jointing kit complete with all accessories including lugs suitable for following size of 3 core, XLPE aluminum conductor cable of 11 KV grade as required. 70 Sq. mm	1	Set		0.00	INR Zero Only			
6	Fixing of street lights with connection testing & commissioning etc. as required.	45	Nos.		0.00	INR Zero Only			
7	Providing of XLPE armored copper cables 25 sq.mm 3.5 core.	16	Meter		0.00	INR Zero Only			
8	Providing and fixing of following rating & braking capacity MCCB with thermo magnetic released and terminal spreaders in existing cubical panel board including drilling holes in cubical panel, making connections etc. as required. 250 A, 50kA, FPMCCB	1	Nos.		0.00	INR Zero Only			
9	Earthing with copper earth plate 600mm x 80mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc. with charcoal/ coke and salt as required.	3	Nos.		0.00	INR Zero Only			
10	Total impact of GST for the purpose of CTC	1	Nos.		0.00	INR Zero Only			
Total in Figu	i res	0.00	INR Zero Only						
Quoted Rate in Words					INR Zero Only				
1		1							