

Bill of quantity for the work Temporary potholes repair of CTR road from Bansgarha mines to PO office check post under Bhurkunda project, Barka-Sayal Area.

Sl. No.	Description of work	Qnty.	Unit	Rate	Amount
1	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401 for grading- I Material	180.08	Cum	2329.00	419406.32
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge.All kinds of soil	180.00	Cum	128.05	23049.00
				Total Rs.	442455.32
				Add GST @18%	79641.96
				Total amount of Rs.	522097.28