

Tender Inviting Authority: Staff officer(E&M), Piparwar Area						
Name of the Work / Contract No:	Repairing / maintenance / erection of LT, O/H Line (440V, Swire system) at 1BR Lower colony and part of 1BR Upper colony of Township (Bachra), under GM Unit, PPR Area.				NIT No. : SO(E&M)/PPR/e-NIT/24-25/58	
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)		Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate (Without Taxes) in Rs. P	BASIC RATE (Without Taxes) In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Dismantling of O/H lines comprising of copper/aluminium O/H conductor,G.I.wire,cross arms, insulators etc.(19 span, 30mtr, 5wire system, 0.214kg/m) =609.9 kg	609.9	kg	64.00		0.00	INR Zero Only
2	Dismantling of pole/street light standard/strut embedded in brick ballast foundation etc.as required.	33	No's	1412.00		0.00	INR Zero Only
3	Supply of PCC Pole 8/9 meter long	27	No's	3810.00		0.00	INR Zero Only
4	Erection of RCC/ PCC pole of following length in brick ballast and ramming the foundation, finishing with 150mm thick cement concrete (1:3:6) layer on top with including excavation and refilling etc as required. Above 8.0 metre and upto 11.0 metre	27	No's	5354.00		0.00	INR Zero Only
5	Erection of all aluminium conductor of 7/3.40mm to 7/4.00mm diameter and above including binding etc. as required. (24 span, 30mtr, 5wire system, 0.214kg/m) =770.4 kg	770.4	kg	147.00		0.00	INR Zero Only
6	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 4 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required .	40	set	1042.00		0.00	INR Zero Only
7	Erection of angle iron/channel iron cross arm on wood/Rcc/ Pcc/ steel tubular/rail pole etc. as required.	40	set	225.00		0.00	INR Zero Only
8	Supplying and erection of stay set complete (galvanised) with 19/20mm dia X 1.8meters long stay rod,anchor plate of size 45cm X 45cm X 7.5mm,thimble,stayclamps,bow tightener,7/3.15 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (cement:3 coarse:6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	19	each	4230.00		0.00	INR Zero Only
9	Supply of Cradling 6/8 SWG G.I. wire for cradling [19x(0.164x30mtrx2)+(0.164x35)] =296 kg	296	kg	63.00		0.00	INR Zero Only
10	Erection of G.I.wire no.8 SWG including binding etc.	296	kg	29.00		0.00	INR Zero Only
11	Supplying and erection of 75 mm X 90 mm shackle insulator with G. I. Bolt, nuts and straps etc. as required .	65	set	145.00		0.00	INR Zero Only
12	Supplying and erection of 100 mm X 80 mm pin insulator complete with G. I. Spindle and nuts etc. as required .	100	set	119.00		0.00	INR Zero Only
13	Supplying and fixing of 32mm dia*2.00 meters long GI pipe (medium class)bracket for mounting of fluorescent/HPMV/HP*SV street light fitting on pole including the pipe to the required shape, 2nos 40mm*3mm flate iron clamps with nuts,bolts and washer, painting the flat iron with primer and finish paint etc. as required.	25	each	1228.00		0.00	INR Zero Only
14	Supply & fixing of Phase Separator (Spacer). 24 span x 4 =72	96	No's	643.31		0.00	INR Zero Only
15	Fixing of LED Street Light fitting	25	No's	309.12		0.00	INR Zero Only
16	Supplying and drawing 1 x 1.5 sq. mm sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel PVC conduit as required. For Street light connection	50	mtr	37.00		0.00	INR Zero Only
17	Total impact of GST for the purpose of CTC	1,000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only						