

Item Rate BoQ

Tender Inviting Authority: Dy. Manager(EnM), Central Hospital, Ramgarh						
Name of the Work / Contract No:	Erection of 32 Nos. GI Earthing for different residential quarters (H-type, P-type, T-type, E-type, G-Type, Barracks) & Nursing Hostel of Staff Colony and 05 Nos. of copper earthing at different location in Hospital premises with installation of Lightning Protection at Central Hospital, Ramgarh.				CCL/CHR/E&M/e-Tender/2024-25/08	
Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)		Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate (Without Taxes) in Rs. P	BASIC RATE (Without Taxes) In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.01	Earthing with G.I. earth Plate 600 mm x 600 mm x 6 mm thick including accessories, and providing masonry with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/coke and salt as required.	32.00	Set			0.00	INR Zero Only
1.02	Providing and laying earth connection from earth electrode with 6 SWG dia G.I. wire in 15 mm dia G.I. pipe from earth electrode including connection with copper thimble excavation and re-filling as required.	640.00	Mtrs.			0.00	INR Zero Only
1.03	Earthing with copper earth plate 600 mm x 600mm x 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/coke and salt as required.	5.00	Set			0.00	INR Zero Only
1.04	Providing and fixing 25 mm x 5 mm copper strip on surface or in recess for connection etc. as required.	25.00	Mtrs.			0.00	INR Zero Only
1.05	Providing and fixing 4.00 mm dia copper wire on surface or in recess for loop earthing as required.	100.00	Mtrs.			0.00	INR Zero Only
1.06	Providing and fixing of lightning conductor finial, made of 25 mm dia 300 mm long, copper tube, having single prong at top, with 85 mm dia 3 mm thick copper base plate including holes etc. complete as required.	5.00	Nos.			0.00	INR Zero Only
1.07	Providing and fixing G.I. tape 20 mm X 3 mm thick on parapet or surface of wall for lightning conductor complete as required.(For horizontal run)	90.00	Mtrs.			0.00	INR Zero Only
1.08	Providing and fixing G.I. tape 20 mm X 3 mm thick on parapet or surface of wall for lightning conductor complete as required.(For Vertical run)	200.00	Mtrs.			0.00	INR Zero Only
1.09	Providing and fixing testing joint, made of 20 mm X 3 mm thick copper strip, 125 mm long, with 4 nos. of tinned brass bolts, nuts, chuck nuts and spring washers etc. complete as required.	5.00	Nos.			0.00	INR Zero Only
2	Total impact of GST for the purpose of CTC	1.000	Nos			0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					