

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority: Staff Officer(Civil), Amrapali-Chandragupta Area

:Provision of temporary cabins for 3 Nos. in-motion weigh bridge at Shivpur siding under Amrapali OCP of A-C Area, CCL (e-NIT No: 74 of 2024-25)

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	36.45	cum	188.45	6869.00	INR Six Thousand Eight Hundred & Sixty Nine Only
2	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	6.71	cum	1844.00	12373.24	INR Twelve Thousand Three Hundred & Seventy Three and Paise Twenty Four Only
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources).	8.55	cum	5916.00	50581.80	INR Fifty Thousand Five Hundred & Eighty One and Paise Eighty Only
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class/designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	18.56	cum	5322.15	98779.10	INR Ninety Eight Thousand Seven Hundred & Seventy Nine and Paise Ten Only
5	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 5.1.2 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	2.81	cum	7365.50	20697.06	INR Twenty Thousand Six Hundred & Ninety Seven and Paise Six Only
6	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	109.35	cum	114.40	12509.64	INR Twelve Thousand Five Hundred & Nine and Paise Sixty Four Only
7	Brick work with FPS bricks of class designation 5.0 in superstructure above plinth level upto floor V level in all shapes and sizes in cement mortar 1:6 (1cement:6 coarse sand).	31.71	cum	6494.75	205948.52	INR Two Lakh Five Thousand Nine Hundred & Forty Eight and Paise Fifty Two Only
8	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, uttering,finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	11.10	cum	8797.65	97653.92	INR Ninety Seven Thousand Six Hundred & Fifty Three and Paise Ninety One Only
9	Centering and shuttering including strutting, propping etc. and removal of form for 5.9.5 Lintels, beams, plinth beams, girders, bressumers and cantilevers .	36.00	sqm	470.70	16945.20	INR Sixteen Thousand Nine Hundred & Forty Five and Paise Twenty Only
10	Centering and shuttering including strutting, propping etc. and removal of form for: Weather shade, Chajjas, corbels etc., including edges.	37.49	sqm	637.65	23905.50	INR Twenty Three Thousand Nine Hundred & Five and Paise Fifty Only
11	Centering and shuttering including strutting, propping etc. and removal of form for: Suspended floors, roofs, landings, balconies and access platform.	50.94	sqm	587.10	29906.87	INR Twenty Nine Thousand Nine Hundred & Six and Paise Eighty Seven Only
12	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete .Thermo-Mechanically Treated bars of grade Fe-500D or more.	4088.94	kg	75.85	310146.10	INR Three Lakh Ten Thousand One Hundred & Forty Six and Paise Ten Only
13	Providing and fixing M.S. fan clamp type I or II of 16 mm dia M.S. bar, bent to shape with hooked ends in R.C.C. slabs or beams during laying, including painting the exposed portion of loop, all as per standard design complete.	3.00	each	150.85	452.55	INR Four Hundred & Fifty Two and Paise Fifty Five Only
14	6mm cement plaster mix 1:3 (1cement:6 fine sand).	87.11	sqm	195.85	17060.49	INR Seventeen Thousand &Sixty and Paise Forty Nine Only
15	12mm cement plaster mix 1:6 (1cement:6 fine sand).	285.03	sqm	217.70	62051.03	INR Sixty Two Thousand &Fifty One and Paise Three Only

16	Distemping with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre, of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. Two or more coats on new work.	212.75	sqm	115.00	24466.25	INR Twenty Four Thousand Four Hundred & Sixty Six and Paise Twenty Five Only
17	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade New work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm).	104.04	sqm	111.95	11647.28	INR Eleven Thousand Six Hundred & Forty Seven and Paise Twenty Eight Only
18	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	54.60	kg	92.55	5053.23	INR Five Thousand & Fifty Three and Paise Twenty Three Only
19	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6 mm angle iron and 3 mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer. Using flats 30x6mm for diagonal braces and central cross piece.	14.65	sqm	3730.40	54650.36	INR Fifty Four Thousand Six Hundred & Fifty and Paise Thirty Six Only
20	Providing and fixing M.S. grills of required pattern in frames of windows with MS flats, square or round bars etc. all compl. Fixed to steel windows by welding.	155.52	kg	145.60	22643.71	INR Twenty Two Thousand Six Hundred & Forty Three and Paise Seventy One Only
21	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm.	36.75	sqm	1180.40	43379.70	INR Forty Three Thousand Three Hundred & Seventy Nine and Paise Seventy Only
22	Painting with synthetic enamel paint of app.brand and manufacture to give an even shade. Two or more coats on new work.	22.50	sqm	99.90	2247.75	INR Two Thousand Two Hundred & Forty Seven and Paise Seventy Five Only
23	Costruction of 150 mm x 150 mm open surface drain	152.10	mtr	736.88	112079.45	INR One Lakh Twelve Thousand & Seventy Nine and Paise Forty Five Only
24	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) over 75mm bed of dry brick ballast 40mm nominal size well rammed and consolidated and grouted with fine sand including finishing the top smooth.	24.00	sqm	551.30	13231.20	INR Thirteen Thousand Two Hundred & Thirty One and Paise Twenty Only
25	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : 21.1.1 For fixed portion Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	168.80	kg	367.10	61966.48	INR Sixty One Thousand Nine Hundred & Sixty Six and Paise Forty Eight Only
26	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): 21.3.1 With float glass panes of 4.0 mm thickness (weight not less than 10kg/sqm)	30.69	sqm	824.65	25308.51	INR Twenty Five Thousand Three Hundred & Eight and Paise Fifty One Only
27	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	212.75	sqm	167.75	35688.81	INR Thirty Five Thousand Six Hundred & Eighty Eight and Paise Eighty One Only
28	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor level. Cement mortar 1:4 (1 cement : 4 coarse sand).	9.72	sqm	802.35	7798.84	INR Seven Thousand Seven Hundred & Ninety Eight and Paise Eighty Four Only
29	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	54.93	sqm	871.30	47860.51	INR Forty Seven Thousand Eight Hundred & Sixty and Paise Fifty One Only
30	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	156	sqm	752.85	117444.60	INR One Lakh Seventeen Thousand Four Hundred & Forty Four and Paise Sixty Only
31	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources.	7.28	cum	6490.90	47253.75	INR Forty Seven Thousand Two Hundred & Fifty Three and Paise Seventy Five Only

32	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					1598600.46	INR Fifteen Lakh Ninety Eight Thousand Six Hundred and Paise Forty Six Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words						INR Zero Only