

Bill of Quantity for the work Construction of Ponds in Patratu and Barkagaon Block under CSR Scheme of Barka-Sayal Area (FY 24-25).

Sl. No.	Description of work	Qty.	Unit	Updated rate	Updated Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30 cm in depth, 1.5 sqm in width as well as 10 sqm on plan) including disposal of excavated earth lead up to 50 m and lift up to 1.5 m disposed earth to be leveled and neatly dressed. (All kinds of soils).	9830.00	cum	158.30	1556089.00
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30 cm in depth, 1.5 sqm in width as well as 10 sqm on plan) including disposal of excavated earth lead up to 50 m and lift up to 1.5 m disposed earth to be leveled and neatly dressed. (Soft/Ordinary Rock).	2320.00	cum	307.10	712472.00
3	Extra for every additional lift of 1.5 m or part thereof in all kinds of soil.	3360.00	cum	73.78	247900.80
4	Extra for every additional lift of 1.5 m or part thereof in Ordinary or Hard Rock.	1440.00	cum	132.40	190656.00
		Total Rs.			2707117.80
		GST @18%			487281.20
		Total cost Rs.			3194399.00