

Tender Inviting Authority: Staff officer (E&M), Magadh - Sanghmitra Area, CCL

Name of the Work / Contract No:	Work of " Changing of Previously installed Damaged Flood Light from Weighbridge number 6 to check post number 9 also extension of two number conductor from weighbridge number 7 to kundi village junction for controlling of street lights and tower light under Magadh OCP, M-S Area."	NIT No: G.M.(M-S)/S.O.(E&M)/e-NIT/24-25/71; Dated:- 14.01.2025.
---------------------------------	--	---

Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)
---	---

ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Erection of ACSR conductor of 7/3.35 mm to 7/4.00 diameter and above including binding etc. As required.	195	Kg		0.00	INR Zero Only
2	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 4 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required.	13	Set		0.00	INR Zero Only
3	Erection of Iron / channel iron cross arm on wood /RCC/PCC/steel tubular or Rail pole for 4 wire system.	13	Set		0.00	INR Zero Only
4	Supply of channel iron 75 mm X 40 mm X6 mm (7.14 kg per metre) cross arm for 2 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required.	13	Set		0.00	INR Zero Only
5	Erection of angle Iron / channel iron cross arm on wood/RCC/PCC/steel tubular or Rail pole for 2 wire system.	13	Set		0.00	INR Zero Only
6	Supplying and erection of 100 mm X 80 mm pin insulator complete with G.I. Spindle and nuts etc. As required.	24	Set		0.00	INR Zero Only
7	Supplying and erection of 100 mm X 110 mm Shackle insulator complete with G.I. Bolt, nuts and straps etc. As required.	6	Set		0.00	INR Zero Only
8	Supplying and erection of stay set complete (galvanised) with 19/20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45cm X 7.5 mm, thimble, stay clamps, bow tightener, 7/3.15 mm dia G.I. Stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc.as required.	4	Set		0.00	INR Zero Only
9	Providing and fixing 100A rating and breaking capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubic panel board including drilling holes in cubicle panel, making connections, etc. As required.	2	Each		0.00	INR Zero Only
10	Supplying and drwing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required. 2 X 1.5 sq. Mm	50	Mtr		0.00	INR Zero Only
11	Providing of 100 watt led flood light.	50	Nos		0.00	INR Zero Only
12	Fixing of Supplied item no -11 @ 15 %	1	Job		0.00	INR Zero Only
13	Total impact of GST for the purpose of CTC	1.000	Job	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only	