

**Item Rate BoQ**

Tender Inviting Authority:	PE(EnM)/Kedla Washery.
Name of the Work / Contract No:	Repairing of 415V 4Wire OHL towards riverside of Kedla Washery. NIT No-PO/KW/E-Tender/24-25/ 100 date:- 17.01.2025

Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department				
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (In %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :	Select	18	0.00	0.00	0.00	0.00

**PRICE SCHEDULE**

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Dismantling of pole/Street light standard/strut embedded in cement concrete foundation etc as required	8.00	No.			0.00	INR Zero Only
2	Dismantling of OHL comprising of Cu/Al OH Conductor C.I. Wire, cross arms insulator & etc as required.	200.00	Kg			0.00	INR Zero Only
3	Supplying and erection of galvanised stay set complete with 19/20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm thick, thimble, stay clamps, turn buckle ( 20 mm X 600 mm ), 7/3.15mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand	3.00	No.			0.00	INR Zero Only
4	Erection of steel tubular or rail pole strut in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size ) foundation including excavation and refilling and secured with holding clamps, bolts, nuts, etc. as required.	8.00	Nos.			0.00	INR Zero Only
5	Erection of ACSR conductor of 7/3.35 mm to 7/4.00 diameter and above including binding etc. as required..	200.000	Kg			0.00	INR Zero Only
6	Supplying of channel iron 75 mm X 40 mm X 6 mm cross arm of 4 wire OHL complete with clamps, bolts and nuts including drilling holes for insulator pins, bolts, nuts and washers etc (as per drawing) and painting with primer and finish paint as required	8.000	No.			0.00	INR Zero Only
7	Supply and erection of 440V pin insulator (100mmX80mm) with	15.000	No.			0.00	INR Zero Only
8	Supply and erection of 100mmX110mm shakle insulator with G.I. bolt, nuts and straps etc as required	12.000	No.			0.00	INR Zero Only
9	Cement Concrete 1:3:6 aggregate 40mm nominal sie for strengthening of pole (1mX0.75mX0.6mX8) =3.6m3	3.600	m3			0.00	INR Zero Only
10	Erection of cradle gaurd as required	25.000	No.			0.00	INR Zero Only
11	Supply and fixing of 4pole MCCB type DU-400N, 320-400	1.000	Nos.			0.00	INR Zero Only
12	<b>Total impact of GST for the purpose of CTC</b>	1.00	Nos		0.00	0.00	INR Zero Only
<b>Total in Figures</b>						<b>0.00</b>	INR Zero Only
<b>Quoted Rate in Words</b>	<b>INR Zero Only</b>						