

Tender Inviting Authority: SOEAM,GM Unit Kulu							
Name of the Work / Contract No.:				Renovation of 440V OHL with changing of 07 no. damaged poles, conductor, insulators and making of 03 no. shed for protection of 03 no. Indoor type Transformers at IWSF under Sarabara Project.			
Category of Services (To Be Selected by Department)				Category of Bidder (To Be Selected by Bidder)		To Be Entered by Department	
ITC Available				Works Contract		Bidder's Status (Mandatory)	
Rate of GST (in %)				Total GST (in Rs.)		GST to be Paid By Bidder (in Rs.)	
Name of the Bidder / Bidding Firm / Company :				Select		18	
Total GST (in Rs.)				0.00		0.00	
GST to be Paid By Bidder (in Rs.)				0.00		0.00	
GST to be Paid By CL/Subsidiary (in Rs.)				0.00		0.00	
PRICE SCHEDULE							
(This BOQ template must not be modified/replaced by the bidder and the same should be updated after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Bid Description	Quantity	Units	Estimated Rate in Rs. /	Bidder RATE in Figures To be entered by the Bidder in Rs. /	TOTAL AMOUNT Without Taxes in Rs. /	TOTAL AMOUNT in Words
1	Supply of Cement Pole upto 9 Meter, Wire Load capacity 400 KG.	7.00	Nos			0.00	NR Zero Only
3	Erection of RCC/ PCC pole of following length in back hollow and forming the foundation, finishing with 150mm thick cement concrete (1:3:6) layer on top with including excavation and refilling etc as required. Above 8.0 metre and upto 11.0 metre	7.00	Nos			0.00	NR Zero Only
4	Supplying and erection of bow stay set complete (galvanized) with 1920 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm x 45 cm x 7.5 mm, double stay clamps, nut buckle (20 mm x 60 cm), 74.00 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregate 40 mm nominal size foundation including excavation and refilling and also with 0.6 m long brace of size 50 mm x 50 mm x 6 mm angle iron with 50 mm dia pulley fixed at one end of the brace as required.	10.00	Nos			0.00	NR Zero Only
5	Supplying of channel iron 75 mm X 40 mm x 6 mm (7.14 kg per metre) cross arm for 4 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as	7.00	Nos			0.00	NR Zero Only
6	Erection of angle iron/channel iron cross arm on wood/RCC/PCC/steel tubular/rod pole etc as req.	7.00	nos			0.00	NR Zero Only
7	Supplying and erection of 100 mm X 110 mm shackle insulator with G.I. bolt, nuts and straps etc as req	32.00	Nos			0.00	NR Zero Only
8	Supplying & erection of 100 mm X 80 mm pin insulator complete with G.I. sprackle and nuts etc as required.	28.00	Nos			0.00	NR Zero Only
9	Supply & erection of LT phase separator 04 wire (PVC/Rubber type) as required	180.00	Nos			0.00	NR Zero Only
10	Supply & erection of GI Wire 8 Swg (SX45+1 SX45) X 0.131 X 155span - 191.91 KG For Croding	574.76	kg			0.00	NR Zero Only
11	supplying and erecting earth pit of minimum bore dia 150mm size, approved make Sole Earthing Electrode consisting Pipes-in-Pipe technology as per IS 3045-1987 made of corrosion free G.I. Pipes with constant ohmic value surrounded by highly conductive compound with high charge dissipation suitable for effective and maintenance free earthing With 3 mtr G.I. Pipes having outer pipe dia of 50mm having 80-200 micron galvanizing, inner pipe dia. of 25mm having 200-250 Micron galvanizing, connection terminal dia. of 22mm in nominal soil with 50 kg (Two Bag) Back filling Compound.	2.00	Nos			0.00	NR Zero Only
12	Supply & erection of 16 Sqmm single core Flexible Aluminium Cable	30.00	mtr			0.00	NR Zero Only
13	Supply and fixing of Aluminium lug 16SQMM	4.00	Nos			0.00	NR Zero Only
14	Erection of ACSB conductor of 7/3.35 mm to 7/4.0 mm dia and above including binding etc as req	465.28	kg			0.00	NR Zero Only
15	Dismantling of over head lines comprising of copper/aluminium over head conductor, G.I. wire, cross arms, insulators etc. as required.	465.28	kg			0.00	NR Zero Only
16	Dismantling of existing damaged pole/street light standard/strut embedded in cement concrete, etc as req.	7.00	Nos			0.00	NR Zero Only
17	Providing and making steel pole collar with cement concrete (1 cement, 3 coarse sand: 6 stone aggregate 20mm) of specified size and shape including form work, plastering if required, curing etc as required	2.00	cum			0.00	NR Zero Only
18	Painting of pole	25.00	Nos			0.00	NR Zero Only
19	Making of Shed						
20	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottom, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	3.84	cum			0.00	NR Zero Only
21	Providing and laying in position cement concrete of specified grade excluding the cost of concreting and shuttering - All work up to plinth level: 1:3:6 (1 Cement: 3 coarse sand (zone-III) derived from natural sources: 6 graded stone aggregate 20 mm nominal size) (1 M X 0.8 M X 0.4 M X 18 nos. 5.76Cum)	5.76	cum			0.00	NR Zero Only
22	fabrication and erection of iron Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, bolting, fixing in position and applying a priming coat of approved steel primer all complete	870.24	kg			0.00	NR Zero Only
23	Providing corrugated G.S. sheet roofing including vertical/curved surface feed with polymer coated) or Linlocks, bolts and nuts 8 mm diameter with bakren and G.I. Impet washers or with G.I. Impet washers lined with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/vertical or curved surfaces), excluding the cost of putrins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than 275 g/m ² 24 X 3 Nos	72.00	sqmm			0.00	NR Zero Only
24	Enamel paint in all shades	1.00	job			0.00	NR Zero Only
25	Total Impact of GST for the purpose of CTC	1.000	RS			0.00	NR Zero Only
Total in Figures						0.00	NR Zero Only
Quoted Rate in Words						INR Zero Only	