

Tender Inviting Authority: Amit Kumar, Dy, Manager(CP), Sawang Washery, Kathara Area							
Name of the Work / Contract No:	Work of laying of PVC cable and PVC Sheathed cable at different place inside and outside of plant premises of Sawang Washery				NIT No. : SGW/KTA/ENM/E-Tender/2024-25/83		Date- 08.02.2025
Category of Services (To Be Selected by Department)			Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract		Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :			Select	18	0.00	0.00	0.00
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.01	Laying of one no. PVC insulated and PVC sheathed/XLPE power cable of 11 KV grade of size upto 120 sq.mm. direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc. as required (180 x 2)	360.00	mtrs.			0.00	INR Zero Only
1.02	Laying and fixing of one no. PVC insulated and PVC sheathed/XLPE power cable of 1.1 KV grade of size above 95 sq.mm. and upto 185 sq.mm. (clamped with 25/40 x 3 MS flat clamp) on cable tray as required. (From 51 BC H/D to Bunker control room)	140.00	mtrs.			0.00	INR Zero Only
1.03	Laying of one no. PVC insulated and PVC sheathed/XLPE power cable of 11 KV grade of size upto 120 sq.mm. direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc. as required. From DG set OCB to Gange switch	115.00	mtrs.			0.00	INR Zero Only
1.04	Laying and fixing of one no. PVC insulated and PVC sheathed/XLPE power cable of 1.1 KV grade of size above 35 sq.mm. (Clamped with 1mm thick saddle) on cable tray as required.	120.00	mtrs.			0.00	INR Zero Only
2	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words			INR Zero Only				