

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Project Engineer (E&M), Dhori (K) Colliery					
Name of the Work / Contract No:	Erection and painting of concertina fence & providing of lighting arrangement at magazine of 7/8 incline under Dhori (K) Colliery				NIT/D(K)/E&M/24-25/28
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be)			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape (R.B.T.) / Springcore (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	800	M		0.00	INR Zero Only
2	Dismantling barbed wire or flexible wire rope in fencing including making rolls and stacking within 50 metres lead.	300	Kg		0.00	INR Zero Only
3	With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel work (double coat) post of fencing including barbed wire and earthing and poles.	200	m2		0.00	INR Zero Only
4	Painting with aluminium paint of approved brand and manufacture to give an even shade . 13.63.1 Two or more coats. post of fencing including barbed wire and earthing and poles.	200	m2		0.00	INR Zero Only
5	Erection of steel tubular or rail pole strut in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling and secured with holding clamps, bolts, nuts, etc. as required	4	no		0.00	INR Zero Only
6	Supplying and erection of stay set complete (galvanised) with 19/20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, bow tightener, 7/ 3.15 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	4	no		0.00	INR Zero Only
7	Erection of all aluminium conductor of 7/1.96 mm to 7/3.10 mm diameter including binding etc. as required. (2 wire x 50m x 5 span x 0.214 Kg/m)	107	No		0.00	INR Zero Only
8	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) crossarm for 2 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required.	8	No		0.00	INR Zero Only
9	Erection of angle iron/ channel iron cross arm on wood/ RCC/ PCC/ steeltubular/ rail pole etc. as required	8	No		0.00	INR Zero Only
10	Fixing of light fittings on pole	8	No		0.00	INR Zero Only
11	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words						INR Zero Only