

Tender Inviting Authority: Staff officer (E&M), NK Area, CCL					
Name of the Work / Contract No:	Repairing, maintenance, reconditioning and re-arrangement of power supply in EOT crane of various shops and control panel of machine shop at Regional Repair Shop Dakra under GM Unit, NK Area			NIT No. GM (NK)/EnM/eNIT/2024-25/220; dated 11.02.2025.	
Category of Services (To Be Selected by Department)			Category of Bidder (To Be Selected by Bidder)		
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

**PRICE SCHEDULE**

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Providing of Corban holder	9.00	Nos		0.00	INR Zero Only
2	Providing of Corban brush	20.00	Nos		0.00	INR Zero Only
3	Providing 4 SWG Copper wire.	37.90	kg		0.00	INR Zero Only
4	Providing & fixing of bobbin insulators with nut and bolts.	120.00	Nos		0.00	INR Zero Only
5	Providing of copper stud for 5MT capacity EOT crane.	15.00	Nos		0.00	INR Zero Only
6	Providing of nut bolts with washer.	120.00	Nos		0.00	INR Zero Only
7	Providing of 3LAO601-1YB heavy duty switch.	5.00	Nos		0.00	INR Zero Only
8	Providing of 8 way pendant station for EOT Crane.	6.00	Nos		0.00	INR Zero Only
9	Providing of 25 Amp. Overload relay.	4.00	Nos		0.00	INR Zero Only
10	Providing of 3 phase 25 Amp. Power contactor.	4.00	Nos		0.00	INR Zero Only
11	Providing of 12 core 2.5 sq.mm multi core flexible copper cable.	60.00	Metre		0.00	INR Zero Only
12	Labour charge for item 1 to 11	1.00	job		0.00	INR Zero Only
13	Applying priming coat With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanized iron works.	734.75	sqm		0.00	INR Zero Only
14	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade Two or more coats	734.75	sqm		0.00	INR Zero Only
15	Supplying, installing, testing and commissioning of following capacity TPN tap off box made of 1.6mm thick sheet steel enclosure duly painted with powder coating on existing rising mains complete with TPN disconnecter FSU and HRC fuses, connections, earthing etc. as required. 200 A TPN	1.00	Nos		0.00	INR Zero Only
16	Supplying, installing, testing and commissioning of following capacity TPN tap off box made of 1.6mm thick sheet steel enclosure duly painted with powder coating on existing rising mains complete with TPN disconnecter FSU and HRC fuses, connections, earthing etc. as required. 100 A TPN	3.00	Nos		0.00	INR Zero Only
17	Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc. with charcoal/ coke and salt as required	5.00	Nos		0.00	INR Zero Only
18	Providing and fixing 25 mm X 5 mm GI. Strip on surface or in recess for connections etc. as required.	30.00	Metre		0.00	INR Zero Only
19	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos	0.00	0.00	INR Zero Only
<b>Total in Figures</b>					0.00	INR Zero Only
<b>Quoted Rate in Words</b>						<b>INR Zero Only</b>