

**Bill of quantity for the work Urgent face-lifting of Old Shiv Mandir Sayal-D for Shivratri under Sayal-D Project .**

SL no	Description of item	Qty	Unit	Updated Rate	Amount
1	Surface dressing of the ground including removing vegetation and in- equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kinds of soil	960.00	sqm	19.75	18960.00
2	Distempering with 1st quality acrylic distemper (ready mixed) having VOC (Volatile Organic Compound ) content less than 50 gram/ litre, of approved brand and of required said and colour complete to give and even said. Old work (one or more coats)	622.18	sqm	38.55	23985.04
3	Finishing walls with Acrylic Smooth exterior paint of required shade: Old work (One or more coat applied @ 0.90 Itr/10 sqm).	638.44	sqm	56.70	36199.55
4	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	211.91	sqm	65.65	13911.89
5	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats @ 2.20 kg/10 sqm) complete.	571.73	sqm	48.35	27642.90
		Total Rs.			120699.38
		Add GST @ 18%			21725.89
		Total cost incl. GST Rs.			142425.27