

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Project Engineer (Mech.), CHP-CPP, Piparwar Area							
Name of the Work / Contract No:	Dismantling 8" diameter pipeline from soil along track of 1016 and 1017 and repairing, welding and fitting with all fittings (like valve, tee, bend, sprocket and rain gun), and placing the pipeline 2' above the ground for dust suppression and cleaning both side of raw coal stock under CHP-CPP, Piparwar Area.				NIT No. : PE(Mech.)/e-NIT/24-25/27		
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department				
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00	
PRICE SCHEDULE							
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate (Excluding GST) in Rs. P	BASIC RATE In Figures To be entered by the Bidder (Without GST) in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Dismantling old CI pipes of 200 mm diameter including excavation and refilling trenches after taking out the pipes, breaking lead caulked joints, melting of lead and making into blocks, including stacking of pipes at site lead up to 50 meter, Quantity = 550 m x 2 no = 1100 m.	1100	M	259.15		0.00	INR Zero Only
2	Laying and Fixing CI pipes of 200 mm diameter 2" above ground. Quantity = 550 m x 2 no. 1100 m.	1100.00	M	142.50		0.00	INR Zero Only
3	Welding of 8 " dia pipeline. Quantity	220000.00	CM	2.95		0.00	INR Zero Only
4	Providing and fitting gun metal gate valve of 80 mm diameter with CI wheel	20	NO	1933.85		0.00	INR Zero Only
5	Finishing with Epoxy paint (two or more coats) at all locations prepared on steel work.	690.8	M2	154.30		0.00	INR Zero Only
6	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only						