

Validate

Print

Help

**Item Rate BoQ**

Tender Inviting Authority: Project Engineer (Elect.), CHP-CPP, Piparwar Area							
Name of the Work / Contract No:	Diversion/relocation of 11 Kv & 440 V O/H line passing nearby W.B No. -01, 02, 03, 04 & wash coal stock yard due to non-maintaining of minimum safety clearance from 33 KV solar power O/H line under CHP-CPP/PPR.On urgent basis before charging the 33 KV solar power.					NIT No. : PE(Elect.)/e-NIT/24-25/38	
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department				
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00	
PRICE SCHEDULE							
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate (Excluding GST) in Rs. P	BASIC RATE In Figures To be entered by the Bidder (Without GST) in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Dismantling of pole/ street light standard/ strut embedded in brick ballast foundation etc. as required.	15	No.	1412.00		0.00	INR Zero Only
2	Erection of steel tubular or rail pole strut in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size ) foundation including excavation and refilling and secured with holding clamps, bolts, nuts, etc. as required.	15	No.	6508.00		0.00	INR Zero Only
3	Supplying and erection of bow stay set complete (galvanised) with 19/20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, turn buckle ( 20 mm X 60 cm ), 7/ 4.00 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size ) foundation including excavation and refilling and also with 0.6 m long brace of size 50 mm X 50 mm X 6 mm angle iron with 50 mm dia pulley fixed at one end of the brace as required.	8	SET	4830.00		0.00	INR Zero Only
4	Supplying and erection of 100 mm X 80 mm pin insulator complete with G. I. Spindle and nuts etc. as required .	15	SET	119.00		0.00	INR Zero Only
5	Supplying and erection of 11 KV disc insulator for 11 KV over head lines with galvanised insulator fittings, ball and socket type and complete with galvanised strain clamps, bolts, nuts, washers etc. as required.	6	SET	818.00		0.00	INR Zero Only

6	Supplying and erection of 11 KV pin insulator complete with large steel head G.I. pin, nuts, washers etc. as required.	6	SET	249.00		0.00	INR Zero Only
7	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 4 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required .	20	SET	1042.00		0.00	INR Zero Only
8	Dismantling of over head lines comprising of copper/ aluminium over head conductor, G.I. wire, cross arms, insulators etc. as required. 50 mtr. X 15 span x 5 no = 3750 mtr x 0.214 kg/km = 802.5	802.5	KG	64.00		0.00	INR Zero Only
9	Erection of all aluminium conductor of 7/1.96 mm to 7/3.10 mm diameter including binding etc. as required. 50 mtr. X 13 span x 5 no = 3250 mtr x 0.214 kg/km = 695.5	695.5	KG	190.00		0.00	INR Zero Only
10	Supplying and making outdoor cable end termination with heat shrinkable jointing kit complete with all accessories including ferrules suitable for following size of 3 core, XLPE aluminium conductor cable of 11 KV grade as required : 70 Sq. MM	2	No.	15878.00		0.00	INR Zero Only
11	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required.Upto 35 sq. mm	60	Mtr.	277.00		0.00	INR Zero Only
12	Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	4	No.	6101.00		0.00	INR Zero Only
13	supply and erection of 35 Sq mm. Bunch cable (3 x 35 + 1 x 16 + 1 x 25 Sq. mm)	450	Mtr.	382.99		0.00	INR Zero Only
14	Providing & fixing of suspension Clamp for Stringing of Cable .On top of Pole.	15	No.	1216.94		0.00	INR Zero Only
15	Painting charges of steel tublor and rail pole	15	No.	655.49		0.00	INR Zero Only
16	supply and erection of 35 Sq mm. 4 core aluminium armour cable.	100	Mtr.	406.77		0.00	INR Zero Only
17	Aluminium lugs for 70 sq. mm cable	40	No.	16.95		0.00	INR Zero Only
18	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos		0.00	0.00	INR Zero Only
<b>Total in Figures</b>						<b>0.00</b>	INR Zero Only
<b>Quoted Rate in Words</b>					<b>INR Zero Only</b>		