

Tender Inviting Authority: SOE&M, GM Unit Kuju							
Name of the Work / Contract No:	Laying and dismantling of 150mm dia MS/GI Pipeline at Karma Project Under Kuju Area.				NIT No. : GM (K)EnM/e-Tender/24-25/271		
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department				
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00	
<b>PRICE SCHEDULE</b>							
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
2	Laying and erection of G.I/MS pipes 150mm dia	350.00	Mtr			0.00	INR Zero Only
3	Providing jointing of G.I pipe including cost of nut and bolts and testing of: 150 mm diameter pipe	53.00	Nos			0.00	INR Zero Only
4	Providing and fixing flanges of 150 mm dia pipe including welding.	60.00	Nos			0.00	INR Zero Only
5	Providing and fixing bend of 150 mm dia pipe including welding	4.00	Nos			0.00	INR Zero Only
6	Providing and fixing TEE of 150 mm dia pipe	4.00	Nos			0.00	INR Zero Only
7	Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately) 150mm diameter.	2.00	Nos			0.00	INR Zero Only
8	Supply & Fixing of Foot Valve 6"	2.00	Nos			0.00	INR Zero Only
9	Supply & Fixing of NR Valve 6"	2.00	Nos			0.00	INR Zero Only
10	Dismantling, Installation and alignment of Pump set 2000GPM/1000GPM/500GPM with connection etc by providing man power	2.00	job			0.00	INR Zero Only
11	Dismantling of G.I/MS pipes 150mm dia	350.00	Mtr			0.00	INR Zero Only
12	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth upto 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m: Pipes, cables etc. exceeding 80 mm dia. but not exceeding 300 mm dia	150.00	Mtr			0.00	INR Zero Only
13	<b>Total impact of GST for the purpose of CTC</b>	1.000 nos				0.00	INR Zero Only
<b>Total in Figures</b>						0.00	INR Zero Only
<b>Quoted Rate in Words</b>							INR Zero Only