

Tender Inviting Authority: PROJECT OFFICER, RRS, DAKRA, NK AREA, CCL

Name of the Work / Contract No:	Providing, Installation and fabrication of Bus bar enclosed metal box with fixing of main switch for systematic power distribution in Substation (11kV/440V) at RRS (NK) Area Dakra.	NIT No: PO/RRS/NK/EnM/e-NIT/2024-25/20	Dt. 18.02.2025
---------------------------------	--	--	----------------

Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)
---	---

ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Metallic bus bar box 1.9X1.5X0.5 Meter including fabrication work with angle, channel & M.S sheet and painting with red oxide & synthetic paint etc. as required.	1	Set		0.00	INR Zero Only
2	Providing of commercial copper strip com grade 50X5 mm.	21.16	kg		0.00	INR Zero Only
3	Providing of bus bar insulator 415 Volt.	16	Nos.		0.00	INR Zero Only
4	Providing of 16 sq.mm ISI marked FRLS insulated single core copper cable.	50	Meter		0.00	INR Zero Only
5	Providing of copper lugs 50 sq.mm heavy duty.	35	Nos.		0.00	INR Zero Only
6	Contractors profit on item no. 2 to 5.	1	Job		0.00	INR Zero Only
7	Providing and fixing following rating and breaking capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required. 800 A, 50 KA,TPMCCB	1	Nos.		0.00	INR Zero Only
8	Supplying, installing, testing and commissioning of following capacity TPN tap off box made of 1.6mm thick sheet steel enclosure duly painted with powder coating on existing rising mains complete with TPN disconnecter FSU and HRC fuses, connections, earthing etc. as required. 400 A TPN	3	Nos.		0.00	INR Zero Only
9	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	75.6	Kg		0.00	INR Zero Only
10	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than 275 gm./ m ²	42	Sqm.		0.00	INR Zero Only
11	Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc. with charcoal/ coke and salt as required	3	Nos.		0.00	INR Zero Only
12	Providing and fixing 25 mm X 5 mm GI. Strip on surface or in recess for connections etc. as required.	30	Meter		0.00	INR Zero Only
13	Total impact of GST for the purpose of CTC	1	Nos.		0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only	