

Tender Inviting Authority: PROJECT OFFICER, RRS, DAKRA, NK AREA, CCL						
Name of the Work / Contract No:	Laying of power cables in trenches with required jointing kit, lugs and tags at R.R.S (NK) Dakra under GM Unit, NK Area.			NIT No: PO/RRS/NK/EnM/e-NIT/2024-25/21		Dt. 18.02.2025
Category of Services (To Be Selected by Department)			Category of Bidder (To Be Selected by Bidder)			
TTC Available	Works Contract		Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :			Select	0.00	0.00	0.00
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 kV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc. as required. 95 Sq.mm	140	Meter		0.00	INR Zero Only
2	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 kV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc. as required. 120 Sq.mm	140	Meter		0.00	INR Zero Only
3	Supplying and making outdoor cable end termination with heat shrinkable jointing kit complete with all accessories including lugs suitable for following size of 3 core, XLPE aluminum conductor cable of 11 KV grade as required. 95 Sq.mm	1	Nos.		0.00	INR Zero Only
4	Supplying and making outdoor cable end termination with heat shrinkable jointing kit complete with all accessories including lugs suitable for following size of 3 core, XLPE aluminum conductor cable of 11 KV grade as required. 120 Sq.mm	1	Nos.		0.00	INR Zero Only
5	Providing and fixing of transparent industrial PVC cable tie.	200	Nos.		0.00	INR Zero Only
6	Providing and fixing of heavy duty copper tubular terminals. 95 sq.mm	12	Nos.		0.00	INR Zero Only
7	Providing and fixing of heavy duty copper tubular terminals. 120 sq.mm	8	Nos.		0.00	INR Zero Only
8	Total impact of GST for the purpose of CTC	1	Nos.		0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words			INR Zero Only			