

Tender Inviting Authority: Staff Officer Civil Piparwar Area.

Name of Work : Backside PCC and drain repair at 4 blocks of MQ type qrts at 122 colony under GM Unit, Piparwar Area

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
SI. No.	Item Description	Quantity	t	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1.01	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30cm in depth, 1.5m in width as well as 10sqm on plan) including getting out and disposal of excavated earth to a depth upto 50m and for all lift, as directed by Engineer-in-charge. All kinds of soil	158.100	Cum	128.05	20244.71	INR Twenty Thousand Two Hundred & Forty Four and Paise Seventy One Only
1.02	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	29.200	Cum	1844.00	53844.80	INR Fifty Three Thousand Eight Hundred & Forty Four and Paise Eighty Only
1.03	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8(1Cement:4coarse sand(zone-III) derived from natural sources:8 graded stone aggregate 40 mm nominal size derived from natural sources)	2.800	Cum	5167.75	14469.70	INR Fourteen Thousand Four Hundred & Sixty Nine and Paise Seventy Only
1.04	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement-All work up to plinth level :1:1.5:3(1cement:1.5coarse sand(zone-III) derived from natural sources: 3 graded stone aggregate 20 mm nominal size derived from natural sources)	18.060	Cum	7365.50	133020.93	INR One Lakh Thirty Three Thousand & Twenty and Paise Ninety Three Only
1.05	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	1264.200	KG	75.85	95889.57	INR Ninety Five Thousand Eight Hundred & Eighty Nine and Paise Fifty Seven Only

1.06	Centering and shuttering including strutting, propping etc. and removal of form work for: Foundations, footings, bases for columns	224.000	sqm	262.55	58811.20	INR Fifty Eight Thousand Eight Hundred & Eleven and Paise Twenty Only
1.07	Filling available excavated earth (excluding rock) in trenches, plinth. sides of foundation etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50m and for all lift	52.700	Cum	114.40	6028.88	INR Six Thousand & Twenty Eight and Paise Eighty Eight Only
1.08	Brick edging in full brick width and half brick depth including excavation, refilling and disposal of surplus earth lead upto 50 metres. With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	528.000	sqm	147.80	78038.40	INR Seventy Eight Thousand & Thirty Eight and Paise Forty Only
1.09	Providing and laying in position cement concrete of specified gr 1:2:4 (1 cement :2 coarse sand (zone-III) derived from natural sources :4 graded stone aggregate 20 mm nominal size derived from natural sources)	52.800	Cum	6490.90	342719.52	INR Three Lakh Forty Two Thousand Seven Hundred & Nineteen and Paise Fifty Two Only
1.10	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					803067.71	INR Eight Lakh Three Thousand & Sixty Seven and Paise Seventy One Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				