

Item Rate BoQ

Tender Inviting Authority: Staff Officer (Civil) Hazaribagh Area

Name of the Work / Contract No: Repairing of the road at 38 no. colony of Tapin North OCP under Hazaribagh Area

Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (In %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.01	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:1½:3 (1 Cement: 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	425.48	Cum			0.00	INR Zero Only
1.02	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m	900.00	Sqm			0.00	INR Zero Only
1.03	Supplying and filling in plinth with Jamuna sand under floors, including watering, ramming, consolidating and dressing complete.	60.75	Cum			0.00	INR Zero Only
1.04	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	7.20	Cum			0.00	INR Zero Only
1.05	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete	251.40	Sqm			0.00	INR Zero Only
1.06	Providing and laying factory made chamfered edge Cement Concretepaver blocks in footpath, parks, lawns, drive ways or light trafficparking etc, of required strength, thickness & size/ shape, made bytable vibratory method using PU mould, laid in required colour &pattern over 50mm thick compacted bed of sand, compacting andproper embedding/laying of inter locking paver blocks into the sandbedding layer through vibratory ompaction by using plate vibrator,filling the joints with sand and cutting of paver blocks as per requiredsize and pattern, finishing and sweeping extra sand. complete all asper direction of Engineer - in - Charge.60mm thick cement concrete paver block of M-35 gradewith approved colour, design & pattern.	1250.00	Sqm			0.00	INR Zero Only
1.07	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	15.00	Cum			0.00	INR Zero Only
1.08	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand)	196.00	Sqm			0.00	INR Zero Only
1.09	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	39.60	Cum			0.00	INR Zero Only
1.10	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete up to plinth level. Thermo-Mechanically Treated bars	576.00	Kg			0.00	INR Zero Only
2.00	Total impact of GST for the purpose of CTC	1.000	Nos			0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only						