

Tender Inviting Authority: PE (Civil) Karo OCP

Name of Work: Temporary room for STP near Jawahar Nagar,CISF check post under Karo OCP of BnK Area.

Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department		
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	Earth work in excavation by mechanical means (Hydraulic excavator) manually over areas (exceeding 30cm in depth 1.5 m in wall as 10 Sq.m on plan) including disposal excavated earth lead up to 50m and lift upto 1.5m disposed earth to be leveled and neatly dressed. All kind of soil	7.300	Cum	188.45	1375.69	INR One Thousand Three Hundred & Seventy Five and Paise Sixty Eight Only
2	Supplying and filling in plinth with Jamuna sand under floors, including watering, ramming, consolidating and dressing complete.	2.240	Cum	1844.00	4130.56	INR Four Thousand One Hundred & Thirty and Paise Fifty Six Only
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	2.840	Cum	5916.00	16801.44	INR Sixteen Thousand Eight Hundred & One and Paise Forty Four Only
4	Brick work with common burnt clay F.P.S. brick of class designation 7.5 in foundation and plinth in :Cement mortar 1:6 (1 cement : 6 coarse sand)	4.550	Cum	5322.15	24215.78	INR Twenty Four Thousand Two Hundred & Fifteen and Paise Seventy Eight Only
5	Brick work with common burnt clay F.P.S. bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :: Cement mortar 1:6 (1 cement : 6 coarse sand)	14.850	Cum	6494.75	96447.04	INR Ninety Six Thousand Four Hundred & Forty Seven and Paise Four Only
6	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	157.200	Kg	92.55	14548.86	INR Fourteen Thousand Five Hundred & Forty Eight and Paise Eighty Six Only
7	12 mm cement plaster of mix 1:6 (1 cement : 6 fine sand)	129.590	Sqm	217.70	28211.74	INR Twenty Eight Thousand Two Hundred & Eleven and Paise Seventy Four Only
8	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate	21.900	Sqm	452.50	9909.75	INR Nine Thousand Nine Hundred & Nine and Paise Seventy Five Only
9	Colour washing such as green, blue or buff to give an even shade : New work (two or more coats) with a base coat of white washing with lime	129.590	Sqm	33.40	4328.31	INR Four Thousand Three Hundred & Twenty Eight and Paise Thirty One Only
10	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	66.060	Kg	77.95	5149.38	INR Five Thousand One Hundred & Forty Nine and Paise Thirty Eight Only
11	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling / self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	30.820	Sqm	571.00	17598.22	INR Seventeen Thousand Five Hundred & Ninety Eight and Paise Twenty Two Only
12	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	9.920	Sqm	99.90	991.01	INR Nine Hundred & Ninety One and Paise One Only
13	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					223707.77	INR Two Lakh Twenty Three Thousand Seven Hundred & Seven and Paise Seventy Seven Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only					