

Tender Inviting Authority: SOE&M, GM Unit Kuju							
Name of the Work / Contract No:	Arrangement of safety relays at secondary side of Transformer installed at mines and substation of Topa OCP Under Kuju Area.				NIT No. : GM (K)/EnM/e-Tender/24-25/272		
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department				
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00	
PRICE SCHEDULE							
(This BOQ template must not be modified/replaced by the bidder and the same should be updated after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
2	Supply and fixing MCCB 250A, 4 Pole 50Hz, 415V, Breaking capacity 50KA Microprocessor Based Release having (a) adjustable overload setting from 0.4 to 1 xin. (b)Adjustable short circuit setting from 1.5 to 8 xlr. (c)Inbuilt instantaneous protection (d)Inbuilt ground fault protection from 20% to 50% of in. (e)Adjustable neutral overload protection from 50% to 150% of ir. (f)Front LED Indication. (g)Panel mounted display for current metering & trip record.	6.00	Nos			0.00	INR Zero Only
3	Supply and fixing of 250 TPN Switch disconnector fuse unit with ss Enclosure with Door interlock & Padlock facility. Including cable gland boxes	6.00	Nos			0.00	INR Zero Only
4	Supply and fixing of 250 Din Type HRC Fuse Links, with breaking capacity 100KA	12.00	Nos			0.00	INR Zero Only
5	Supply and fixing of Shunt Trip Release 415V AC	6.00	Nos			0.00	INR Zero Only
6	Supply and fixing of Auxilary contact 415V AC, 2C/0	6.00	Nos			0.00	INR Zero Only
7	Supply and fixing of Micro-processor based Earth Leakage relay with CBCT. (300Ma-12A), Suitable for 65mm dia.	6.00	Nos			0.00	INR Zero Only
8	Supply and fixing of Current Transformer for overload & Ammeter 100/5	18.00	Nos			0.00	INR Zero Only
9	Supply and fixing of Indicating lamp with holder	18.00	Nos			0.00	INR Zero Only
10	Supply and fixing of Voltmeter 0-500v (96sqmm):Digital Type, 3 PH	6.00	Nos			0.00	INR Zero Only
11	Supply and fixing of Ameter 100/5 (96sqmm) :Digital Type, 3 PH	6.00	Nos			0.00	INR Zero Only
12	Supply and fixing of SS Enclosure 2x2.5 with powder coated paints, single door, suitable for Installation of above mentioned items.	6.00	Nos			0.00	INR Zero Only
13	Complete wiring with Materials including wire, tape, Lugs Feruls, nut bolt washer with fabrication of SS Enclosure for MCCB.	6.00	Nos			0.00	INR Zero Only
14	Labour Charges for fixing of above testing @10%	1.00	L/S			0.00	INR Zero Only
15	CONTRACTOR'S PROFIT @ 10%	1.00	L/S			0.00	INR Zero Only
16	Total impact of GST for the purpose of CTC	1.000	nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words							INR Zero Only