

Tender Inviting Authority: Staff officer (E&M), NK Area, CCL						
Name of the Work / Contract No:		Diversion of Rohini and Purnadih Colony water supply from Khilawan Dhaura to Sump No. 04 in respect of Rohini OCP, NK Area			NIT No. GM (NK)/EnM/eNIT/2024-25/224; dated 18.02.2025.	
		Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)		
ITC Not Available		Works Contract		Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)
Name of the Bidder/ Bidding Firm / Company :				Select	0.00	0.00
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Transportation of 6" dia Pipe from Stock to work site.	1075.00	Mtr		0.00	INR Zero Only
2	Laying and fixing of 6" dia Pipeline	1075.00	Mtr		0.00	INR Zero Only
3	Dismantling of 4" dia MS/GI Pipe.	900.00	Mtr		0.00	INR Zero Only
4	Transportation of 6" dia MS Pipe (after dismantling).	900.00	Mtr		0.00	INR Zero Only
5	Pipe cutting charge of 6" dia pipe.	150.00	Nos		0.00	INR Zero Only
6	Fixing and making of pipe joints of 6" dia by required welding	190.00	Nos		0.00	INR Zero Only
7	Making of 6" dia pipe bend L type and 120 degree bend as per requirement and laying of both ends with help of gas cutting and welding with proper centering.	15.00	Nos		0.00	INR Zero Only
8	Supply and fixing of 6" dia non return valve	2.00	Nos		0.00	INR Zero Only
9	Supply and fixing of 6" dia sluice value	2.00	Nos		0.00	INR Zero Only
10	Supply and fixing of 6" dia Double Ball type Air Release valve	2.00	Nos		0.00	INR Zero Only
11	Supply of 6" dia flange	8.00	Nos		0.00	INR Zero Only
12	Supply and fixing of MS Nuts and Bolts with washer	60.00	kg		0.00	INR Zero Only
13	Earth work in excavation by mechanical Hydraulic excavator/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 Sqm on plan), including dressing of sides and raming of bottom, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m. All kinds of soil.	1700.00	cum		0.00	INR Zero Only
14	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only	