

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Staff officer (E&M), NK Area, CCL

Name of the Work / Contract No:	Rearrangement of power supply and repairing/ rewiring of various type offices in different location in NK Area, Dakra with inclusion of safety provision in wiring circuit along with lighting arrangement under GM Unit, NK Area	NIT No. GM (NK)/EnM/eNIT/2024-25/225; dated 18.02.2025.			
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required.	66.00	Point		0.00	INR Zero Only
2	Supplying and fixing following modular switch / socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. 5/6 Amp. Switch piano type switch/ socket on the existing switch box/ cover including connections etc. as required. 15/16 amps switch	16.00	Nos		0.00	INR Zero Only
3	Supplying and fixing following size modules, GI box along with modular base & cover plate for modular switches in recess etc. as required. 2 Module (75mmX75mm)	8.00	Nos		0.00	INR Zero Only

4	Supplying and fixing following size modules, GI box along with modular base & cover plate for modular switches in recess etc. as required 4 Module (125mmX75mm)	4.00	Nos		0.00	INR Zero Only
5	Supplying and fixing following size modules, GI box along with modular base & cover plate for modular switches in recess etc. as required 8 Module (125mmX125mm)	7.00	Nos		0.00	INR Zero Only
6	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required.	120.00	Point		0.00	INR Zero Only
7	Supplying and fixing metal box of 180mm X 100mm X 60mm deep(nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 6 pin 5/6 & 15/16 amps socket outlet and 15/16 amps piano type switch, connection, painting etc. as required.	26.00	Nos		0.00	INR Zero Only
8	Supplying and fixing metal box of 150mm X 75mm X 60mm deep(nominal size) on surface or in recess with suitable size of phenol laminated sheet cover in front including providing and fixing 3 pin5/6 amps socket outlet and 5/6 amps piano type switch, connection, painting etc. as required. (For light plugs to be used in nonresidential buildings).	20.00	Nos		0.00	INR Zero Only
9	Supplying and fixing stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	13.00	Nos		0.00	INR Zero Only
10	Supplying and fixing 3 pin, 5 amp ceiling rose on the existing junction box/ wooden block including connection etc. as required	41.00	Nos		0.00	INR Zero Only
11	Supplying and fixing brass batten/ angle holder including connection etc. as required.	84.00	Nos		0.00	INR Zero Only
12	Supplying, installing, testing and commissioning of following capacity TPN tap off box made of 1.6mm thick sheet steel enclosure duly painted with powder coating on existing rising mains complete with TPN disconnecter FSU and HRC fuses, connections, earthing etc. as required. 63 A TPN	2.00	Nos		0.00	INR Zero Only
13	Supplying, installing, testing and commissioning of following capacity TPN tap off box made of 1.6mm thick sheet steel enclosure duly painted with powder coating on existing rising mains complete with TPN disconnecter FSU and HRC fuses, connections, earthing etc. as required 100 A TPN	4.00	Nos		0.00	INR Zero Only
14	Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required. 2X2.5 sq.mm + 1X2.5 Sq.mm earth wire	200.00	Mtr		0.00	INR Zero Only
15	Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required 2X4 sq.mm + 1X4 Sq.mm earth wire	310.00	Mtr		0.00	INR Zero Only

16	Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required 2X6 sq.mm + 1X6 Sq.mm earth wire	220.00	Mtr		0.00	INR Zero Only
17	Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required 2X10 sq.mm + 1X10 Sq.mm earth wire	250.00	Mtr		0.00	INR Zero Only
18	Supplying and fixing call bell/ buzzer suitable for single phase, 230 volts, complete as required.	9.00	Nos		0.00	INR Zero Only
19	Providing of Exhaust fan 300mm.	4.00	Nos		0.00	INR Zero Only
20	Providing of bus bar 100Amp	3.00	Nos		0.00	INR Zero Only
21	Providing of Changeover switch 100Amp.	2.00	Nos		0.00	INR Zero Only
22	Providing of LED post lamp 35W.	12.00	Nos		0.00	INR Zero Only
23	Providing of aesthetically designed 1X1, 18W LED flat for surface mounting which provides soft light and glare free symmetrical illumination.	32.00	Nos		0.00	INR Zero Only
24	CPOH on item no. 13 to 17	1.00	job		0.00	INR Zero Only
25	Providing and fixing of distribution box enclosure on surface/ recessed along with 240V MCB with connection testing & commissioning etc. as required.	12.00	Nos		0.00	INR Zero Only
26	Erection of steel tubular or rail pole strut in cement concrete 1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required. Above 11.00 meters and up to 13.00 meter.	2.00	Nos		0.00	INR Zero Only
27	12 mm cement plaster of mix 1:6 (1 cement: 6 fine sand)	82.00	sqm		0.00	INR Zero Only
28	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	82.00	sqm		0.00	INR Zero Only
29	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ liter, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour Two coats	300.00	sqm		0.00	INR Zero Only
30	Providing and fixing following capacity TP&N disconnecter fuses witch unit inside the existing panel board with ISI marked HRC fuses including drilling holes in cubicle panel, making connections, etc. as required. 32 Amp TP&N	7.00	Nos		0.00	INR Zero Only

31	Supplying and fixing of DP sheet steel enclosure on surface/ recess along with 32 amps, 240Volts "C" curve DP MCB complete with connections, testing and commissioning etc. as required.	19.00	Nos		0.00	INR Zero Only
32	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required. 5/6 amps switch	10.00	Nos		0.00	INR Zero Only
33	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required. 3 pin 5/6 amp socket outlet	10.00	Nos		0.00	INR Zero Only
34	Earthing with copper earth plate 600mm x 600mm x 3mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc. with charcoal/ coke and salt as required.	3.00	Nos		0.00	INR Zero Only
35	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				