

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority: Staff Officer(Civil), Magadh-Sanghmitra Area

Name of Work : Providing and Fixing of pillars for plotting of land at R&R sites under Magadh OCP of Magadh-Sanghmitra Area. (e NIT No. 56 of 2024-25)

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains not exceeding 1.5 m in width or 10 sqm on plan including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed within ahead of 50m.	62.50	cum	217.31	13581.88	INR Thirteen Thousand Five Hundred & Eighty One and Paise Eighty Eight Only
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	46.87	cum	6458.69	302718.80	INR Three Lakh Two Thousand Seven Hundred & Eighteen and Paise Eighty Only
3	Providing, hoisting and fixing upto floor five level precast reinforced cement concrete work in string courses, bands, copings, bed plates, anchor blocks, plain window sills and the like including the cost of required centring, shuttering, finishing smooth with 6mm thick cement plaster 1:3 (1 cement :3 fine sand) on exposed surfaces complete but excluding cost of reinforcement with 1:2:4 (1cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size).	28.13	cum	7863.87	221210.66	INR Two Lakh Twenty One Thousand Two Hundred & Ten and Paise Sixty Six Only
4	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete .Thermo-Mechanically treated bars	1547.15	Kg	73.21	113266.85	INR One Lakh Thirteen Thousand Two Hundred & Sixty Six and Paise Eighty Five Only
5	Carriage and fixing of pre-cast pillars, wherever required as per the instruction of EIC.	30.00	Days	4599.54	137986.20	INR One Lakh Thirty Seven Thousand Nine Hundred & Eighty Six and Paise Twenty Only
6	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					788764.39	INR Seven Lakh Eighty Eight Thousand Seven Hundred & Sixty Four and Paise Thirty Nine Only
Quoted Rate in Figures		Select			0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only					