

Tender Inviting Authority: Project Engineer (E&M), Ashok OCP, Piparwar Area						
Name of the Work / Contract No:	Erection of 440v OH line (18 span) for illuminating newly constructed haul road from TSS 4202 to departmental working face (2) relocation of 440v OH lighting line behind PPR parking for upcoming dumper parking under ppr patch under Ashok project, PPR Area.				NIT No. : PO(AK)/PE(EnM)/e-NIT/24-25/61	
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)		Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate (With taxes) in Rs. P	BASIC RATE (Without taxes) In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Erection of metallic pole of following length in cement concrete 1:3:6 (1 cement: 3 coarse sand:6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	26	Each	7424.56		0.00	INR Zero Only
2	Erection of all aluminium conductor of 7/1.96 mm to 7/3 10 mm diameter including binding etc. as required	737.64	Kg	224.2		0.00	INR Zero Only
3	Supplying and erection of stay set complete (galvanised) with 19/20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, turn buckle (20 mm X60 cm), 7/4 00 mm dia GI stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement:3 coarse sand:6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required	14	Nos.	5326.52		0.00	INR Zero Only
4	Erection of angle iron/ channel iron cross arm on wood/ RCCI PCCI steel tubular/ rail pole etc. as required.	35	Set	265.5		0.00	INR Zero Only
5	Supplying and erection of 75 mm X 90 mm shackle insulator with G. I. Bolt, nuts and straps etc. as required	72	Set	171.1		0.00	INR Zero Only
6	Supplying and erection of 100 mm X 65 mm pin insulator complete with G. I Spindle and nuts etc. as required	64	Set	140.42		0.00	INR Zero Only
7	Erection of G.I. Wire No. 8 SWG including binding etc. as required.	120	Kg	34.22		0.00	INR Zero Only
8	Dismantling of pole/ street light standard/ strut embedded in brick ballast foundation etc. as required.	8	Each	1666.16		0.00	INR Zero Only
9	Dismantling of over head lines comprising of copper/ aluminium over head conductor, GI wire, cross arms, insulators etc. as required.	319.68	Kg	75.52		0.00	INR Zero Only
10	Earthing with copper earth plate 600 mm X 600 mm X3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required	2	Set	13785.94		0.00	INR Zero Only
11	Making of one length of angle iron 50mm x 50mm x 6mm, 4.5 kg/m single pole cross arm for Four wire 440v over head line complete with clamps, bolts and nuts for clamping to poles 50mm x 6mm,including drilling holes for insulator fittings as required	27	Set	499.8008		0.00	INR Zero Only
12	Making of one length of angle iron 50mm x 50mm x 6mm, 4.5 kg/m Toui vwie 440v over head line complete with clamps, bolts and nuts for clamping to poles 50mm x 6mm,including drilling holes for insulator fittings as required.	6	Set	597.9886		0.00	INR Zero Only
13	Making of one length of angle iron 50mm x 50mm x 6mm, 4.5 kg/m cradle guard arm for Four wire 440v over head line complete with clamps, bolts and nuts for clamping to poles 50mm x 6mm,including drilling holes for insulator fittings as required	4	Set	598.673		0.00	INR Zero Only
14	Supply of 8 SWG GI wire. (Note- Rate taken as per 6 swg GI wire from CPWD 2022 for per Kg)	120	kg	74.34		0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words						INR Zero Only	