

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: PROJECT OFFICER, RRS, DAKRA, NK AREA, CCL						
Name of the Work / Contract No:	Repairing, maintenance and fabrication of metallic structure and installation of main Switches, Earth pits with required accessories in EOT Crane Shops at Regional Repair Shop (NK) Dakra, under G.M Unit, NK Area.			NIT No: PO/RRS/NK/e-NIT/2024-25/23		Dt. 19.02.2025
Category of Services (To Be Selected by Department)			Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract		Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :			Select	0.00	0.00	0.00
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Laying of one number additional PVC insulated and PVC sheathed! XLPE power cable of 1.1 KV grade of following size direct in ground in the same trench in one tier horizontal formation including excavation, sand cushioning, protective covering and refilling the trench etc. as required. Upto 95 sq. mm	40	Meter		0.00	INR Zero Only
2	Supplying and erection of galvanized 'D iron clamps complete with GI bolts, nuts and washers, coach screws etc. as required.	60	Nos.		0.00	INR Zero Only
3	Earthing with copper earth plate 600mm x 600mm x 3mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc. with charcoal/ coke and salt as required.	5	Set		0.00	INR Zero Only
4	Providing and fixing 25 mm X 5 mm GI. Strip on surface or in recess for connections etc. as required.	30	Meter		0.00	INR Zero Only
5	Installation of 1.9X1.5X0.5 meter of switch panel including fabrication work with angle, channel & iron sheet and painting work etc. as required.	5	Nos.		0.00	INR Zero Only
6	Fixing of main switches with making connections etc. as required.	20	Nos.		0.00	INR Zero Only
7	Providing of 95 Sqmm. copper lugs.	24	Nos.		0.00	INR Zero Only
8	Providing of 70 Sqmm. copper lugs.	20	Nos.		0.00	INR Zero Only
9	Providing of 35 Sqmm. copper lugs.	40	Nos.		0.00	INR Zero Only
10	CPOH on item no. 7, 8 & 9.	1	Job		0.00	INR Zero Only
11	Total impact of GST for the purpose of CTC	1	Nos.		0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only	