

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority: Staff Officer(Civil), NK Area.

Name of Work: Repairing of Diesel Dispensing Unit at Dakra Office Under Dakra Project,NK Area

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of Asbestos Cement sheet	34.00	sqm	45.8	1557.20	INR One Thousand Five Hundred & Fifty Seven and Paise Twenty Only
2	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge In cement mortar	5.92	cum	1194.45	7071.14	INR Seven Thousand & Seventy One and Paise Fourteen Only
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:6(1 cement: 6 coarse sand)	5.92	cum	6494.75	38448.92	INR Thirty Eight Thousand Four Hundred & Forty Eight and Paise Ninety Two Only
4	12 mm cement plaster of mix 1:6 (1 cement: 6 fine sand) Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	185.50	sqm	249.7	46319.35	INR Forty Six Thousand Three Hundred & Nineteen and Paise Thirty Five Only
5	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	117.12	kg	92.55	10839.46	INR Ten Thousand Eight Hundred & Thirty Nine and Paise Forty Six Only
6	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) of total coated thickness 0.50mm (base metal of minimum 0.45mm thickness with total coating thickness of 0.05mm) with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	34.00	sqm	571	19414.00	INR Nineteen Thousand Four Hundred & Fourteen Only
7	Extra for providing and fixing wind ties of 40x 6 mm flat iron section.	25.50	meter	138.75	3538.13	INR Three Thousand Five Hundred & Thirty Eight and Paise Twelve Only

8	Providing and fixing T-iron frames for doors, windows and ventilators of mild steel Tee-sections, joints mitred and welded, including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer.Fixing with 15x3 mm lugs 10 cm long embedded in cement concrete block 15x10x10 cm of C.C. 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).	106.20	kg	96.45	10242.99	INR Ten Thousand Two Hundred & Forty Two and Paise Ninety Nine Only
9	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6 mm angle iron and 3 mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer .Using flats 30 X 6 MM for diagonal braces and central cross piece	7.50	sqm	3730.4	27978.00	INR Twenty Seven Thousand Nine Hundred & Seventy Eight Only
10	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to steel windows by welding	43.20	kg	145.6	6289.92	INR Six Thousand Two Hundred & Eighty Nine and Paise Ninety Two Only
11	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	62.40	kg	434	27081.60	INR Twenty Seven Thousand & Eighty One and Paise Sixty Only
12	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item)With float glass panes of 4.0 mm thickness (weight not less than 10kg/sqm)	7.68	sqm	824.65	6333.31	INR Six Thousand Three Hundred & Thirty Three and Paise Thirty One Only
13	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. Cement mortar 1:4 (1 cement :4 coarse sand)	1.60	Sqm	802.35	1283.76	INR One Thousand Two Hundred & Eighty Three and Paise Seventy Six Only
14	Providing, hoisting and fixing above plinth level up to floor five level precast reinforced cement concrete work in string courses, bands, copings, bed plates, anchor blocks, plain window sills and the like, including the cost of required centering, shuttering but , excluding cost of reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	0.18	cum	8356.1	1504.10	INR One Thousand Five Hundred & Four and Paise Ten Only
15	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more	14.40	kg	75.85	1092.24	INR One Thousand & Ninety Two and Paise Twenty Four Only
16	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	36.55	Sqm	98.45	3598.35	INR Three Thousand Five Hundred & Ninety Eight and Paise Thirty Five Only
17	Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gram/litre, of approved manufacturer, of required shade and colour all complete:New work (two or more coats) over and including water thinnable priming coat with cement primer having VOC content less than 50 gram/litre	86.45	Sqm	115	9941.75	INR Nine Thousand Nine Hundred & Forty One and Paise Seventy Five Only
18	Finishing walls with water proofing cement paint of required shade New work (Two or more coats applied @ 3.84 kg/10 sqm)	99.05	sqm	74.7	7399.04	INR Seven Thousand Three Hundred & Ninety Nine and Paise Three Only
19	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade Two or more coats on new work	24.97	Sqm	99.9	2494.50	INR Two Thousand Four Hundred & Ninety Four and Paise Fifty Only
20	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete.Size of Tile 600x600 mm	11.86	Sqm	1180.4	13999.54	INR Thirteen Thousand Nine Hundred & Ninety Nine and Paise Fifty Four Only
21	Supplying and installing following size of perforated painted with powder coating M.S. cable trays with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with M.S. suspenders including bolts & nuts, painting suspenders etc as required.600 mm width X 50 mm depth X 2.0 mm thickness	15.00	meter	1157	17355.00	INR Seventeen Thousand Three Hundred & Fifty Five Only
22	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only

Total in Figures			263782.29	INR Two Lakh Sixty Three Thousand Seven Hundred & Eighty Two and Paise Twenty Nine Only	
Quoted Rate in Figures		Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only			

