

Tender Inviting Authority: PROJECT OFFICER, RRS, DAKRA, NK AREA, CCL						
Name of the Work / Contract No:	Providing and fixing of starter in operating machine at different section, and overload relay and power contactors with required accessories in EOT Crane of Machine Shop and STR Shop at Regional Repair Shop (NK) Dakra under GM Unit, NK Area.			NIT No: PO/RRS/NK/e-NIT/2024-25/24	Dt. 21.02.2025	
	Category of Services (To Be Selected by Department)			Category of Bidder (To Be Selected by Bidder)		
ITC Available	Works Contract			Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)
Name of the Bidder/ Bidding Firm / Company :				Select	0.00	0.00
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Providing of DOL starter, operating voltage upto 240/415 Volt, 50/60 Hz, 3 phase, 50 Amp and IP55 degree of protection	8	Nos.		0.00	INR Zero Only
2	Providing of Overload relay, automatic 3 phase, 25 amp. Thermal type, operating temperature range upto 60 degree	6	Nos.		0.00	INR Zero Only
3	Providing of Power contactors, 2NO+2NC, 40 amp. 415 vault, contact voltage upto 480V AC, 50 60 Hz	6	Nos.		0.00	INR Zero Only
4	Providing and fixing 250 A, 35 KA,TPMCCB capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required	2	Nos.		0.00	INR Zero Only
5	Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required. 2X2.5 sq.mm + 1X2.5 Sq.mm earth wire	40	Meter		0.00	INR Zero Only
6	Installation, testing & commissioning with required accessories etc. as required. On item no. 1 to 3 @15%.	1	Job		0.00	INR Zero Only
7	Total impact of GST for the purpose of CTC	1	Nos.		0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words			INR Zero Only			