

Tender Inviting Authority: Project Engineer (E&M), Ashok OCP, Piparwar Area						
Name of the Work / Contract No:	Erection of 7 span of HT OH Line (3.3 kv) as extension of Feeder No.-5 for provision of power to face pump at Departmental Patch (2) Erection of 4 span HT OH line(3.3 kv) as extension of feeder no-1 for provision of power to Excavators in Departmental Patch under Ashok OCP, Piparwar Area.				NIT No. : PO(AK)/PE(EnM)/e-NIT/24-25/66	
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)		Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate (With taxes) in Rs. P	BASIC RATE (Without taxes) In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	Erection of metallic pole (above 10 mtr and upto 12 mtr) in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling and secured with holding clamps, bolts, nuts, etc. as required	21	Nos.	7424.56		0.00	INR Zero Only
2	Supplying and erection of stay set complete (galvanised) with 19/20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, turn buckle (20 mm X 60 cm), 7/ 3.15 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required	20	Nos.	3833.82		0.00	INR Zero Only
3	Erection of double pole 3 wire cross arm for 11KV/ 22KV/ 33 KV over head lines as required.	9	Set	1092.68		0.00	INR Zero Only
4	Erection of pole top/ straight two wire/ V shape two wire, angle iron/ channel iron, cross arm on steel tubular/ rail/ PCC pole for 11/22/33 KV as required	6	Set	482.62		0.00	INR Zero Only
5	Supplying and erection of 11 KV disc insulator for 11 KV over head lines with galvanised insulator fittings, ball and socket type and complete with galvanised strain clamps, bolts, nuts, washers etc. as required	42	Set	965.24		0.00	INR Zero Only
6	Supplying and erection of 11 KV pin insulator for 11 KV over head lines with galvanised insulator fittings, ball and socket type and complete with galvanised strain clamps, bolts, nuts, washers etc. as required.	30	Set	293.82		0.00	INR Zero Only
7	Erection of all aluminium conductor of 7/1.96 mm to 7/3.10mm diameter including binding etc. as required. (1260 + 660 Mtr=1920 mtr) @ 272KG/KM	522	Kg	224.2		0.00	INR Zero Only
8	Supply of 8 SWG GI wire for erection and fabrication cradle guard, cradling with binding etc and for 7/10 Galvanized stay wire for earth wire. (1485 Mtr) @ 0.469Kg/M= 1485 x 0.469 = 696.46 + 84 kg (for cradling) = 384.16 kg	385	Kg	74.34		0.00	INR Zero Only
9	Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required	2	Nos.	7199.18		0.00	INR Zero Only
10	Erection of ring type guard for 7 spans (20 rings/span)	140	Nos.	62.54		0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words							INR Zero Only