

Tender Inviting Authority: Staff officer (E&M), NK Area, CCL						
Name of the Work/ Contract No:		Complete repairing of VCB Switch (A) 3.3kV, 400 Amp. Make Elektroteknika, Sl. No. FS-374, supplying power to face pump feeder and (B) 3.3-6.6kV/110V, CT 120-60/5+5 Amp. Make Elektroteknika, Sl. No. SP/0/400 supplying power to Shovel No. 05 under Dakra Project, NK Area.				
		NIT No. GM (NK)/EnM/eNTI/2024-25/249; dated 20.03.2025.				
Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)				
Works Contract		Bidder's Status (Mandatory)				
ITC Available		Total GST(in Rs.)		GST to be Paid By Bidder (in Rs.)		GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		0.00		0.00		0.00
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	3.3kV, 400 Amp. Make Elektroteknika, Sl. No. FS-374.					
2	Auxiliary Contactor 110V AC	1.00	Nos		0.00	INR Zero Only
3	Indicator 110V AC/DC	4.00	Nos		0.00	INR Zero Only
4	Earth Leakage Relay on/off/test/reset switch	1.00	Nos		0.00	INR Zero Only
5	Push buttons switch	2.00	Nos		0.00	INR Zero Only
6	Copper strip 50x6 mm for bus bar	6.00	Mtr.		0.00	INR Zero Only
7	P.T 3.3kV/110V AC	1.00	Set		0.00	INR Zero Only
8	Voltmeter 96 sqmm PTR 3.3kV/110V AC	1.00	Nos		0.00	INR Zero Only
9	Ammeter 96 sqmm 120-60/5.5 Amp.	1.00	Nos		0.00	INR Zero Only
10	CBCT 3.3kv	1.00	Nos		0.00	INR Zero Only
11	Overcurrent Relay	1.00	Nos		0.00	INR Zero Only
12	Under voltage relay	1.00	Nos		0.00	INR Zero Only
13	Over voltage relay	1.00	Nos		0.00	INR Zero Only
14	Voltmeter Selector switch	1.00	Nos		0.00	INR Zero Only
15	Ammeter selector switch	1.00	Nos		0.00	INR Zero Only
16	HRC fuse HT side	3.00	Nos		0.00	INR Zero Only
17	HRC fuse LT side	3.00	Nos		0.00	INR Zero Only
18	Bushing insulator with stud	3.00	Nos		0.00	INR Zero Only
19	Earth Leakage Relay 110V, 5 Amp.	1.00	Nos		0.00	INR Zero Only
20	Rectifier Capacitor Bank, 110V AC/DC	1.00	Nos		0.00	INR Zero Only
21	Wiring with material (1.5 sqmm Copper wire, lugs etc).	1.00	Nos		0.00	INR Zero Only
22	Mechanism repairing	1.00	Set		0.00	INR Zero Only
23	Denting, painting work	1.00	job		0.00	INR Zero Only
24	Labour charge	1.00	job		0.00	INR Zero Only
25	3.3-6.6kV/110V, CT 120-60/5+5 Amp. Sl. No. SP/0/400.					
26	Auxiliary Contactor 110V AC	1.00	Nos		0.00	INR Zero Only
27	Indicator 110V AC/DC	4.00	Nos		0.00	INR Zero Only
28	Earth Leakage Relay on/off/test/reset switch	1.00	Nos		0.00	INR Zero Only
29	Push buttons switch	2.00	Nos		0.00	INR Zero Only
30	Overcurrent Relay	1.00	Nos		0.00	INR Zero Only
31	P.T 3.3kV/110V AC	1.00	Set		0.00	INR Zero Only
32	Wiring with material (1.5 sqmm Copper wire, lugs etc).	1.00	Nos		0.00	INR Zero Only
33	Copper strip 50x6 mm	12.00	Mtr.		0.00	INR Zero Only
34	CBCT 3.3kv	1.00	Nos		0.00	INR Zero Only
35	HRC fuse HT side	3.00	Nos		0.00	INR Zero Only
36	HRC fuse LT side	3.00	Nos		0.00	INR Zero Only
37	Earth Leakage Relay 110V, 5 Amp.	1.00	Nos		0.00	INR Zero Only
38	Voltmeter 96 sqmm PTR 3.3kV/110V AC	1.00	Nos		0.00	INR Zero Only
39	Ammeter 96 sqmm 120-60/5.5 Amp.	1.00	Nos		0.00	INR Zero Only
40	Denting, painting work	1.00	job		0.00	INR Zero Only
41	Mechanism repairing	1.00	Set		0.00	INR Zero Only
42	Labour charge	1.00	job		0.00	INR Zero Only
43	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only	