

Tender Inviting Authority: Staff Officer (Civil),CCL, Dhori Area

Name of Work-Provision of Drain with Repair and maintenance of 07 Number weigh bridge and cleaning of Joria Nallah under AADOCM of Dhori Area.

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (In Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge. All kinds of soil	420.00	cum	128.05	53781.00	INR Fifty Three Thousand Seven Hundred & Eighty One Only
2	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	7.00	cum	1844.00	12908.00	INR Twelve Thousand Nine Hundred & Eight Only
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	21.00	cum	5916.00	124236.00	INR One Lakh Twenty Four Thousand Two Hundred & Thirty Six Only
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	11681.60	kg	75.85	886049.36	INR Eight Lakh Eighty Six Thousand & Forty Nine and Paise Thirty Six Only
14	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge. All kinds of soil	785.00	cum	128.05	100519.25	INR One Lakh Five Hundred & Nineteen and Paise Twenty Five Only

15	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	4.65	cum	1844.00	8574.60	INR Eight Thousand Five Hundred & Seventy Four and Paise Sixty Only
16	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	13.05	cum	5916.00	77203.80	INR Seventy Seven Thousand Two Hundred & Three and Paise Eighty Only
17	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	26.34	cum	7365.50	194007.27	INR One Lakh Ninety Four Thousand & Seven and Paise Twenty Seven Only
18	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete.	56.80	sqm	262.55	14912.84	INR Fourteen Thousand Nine Hundred & Twelve and Paise Eighty Four Only
19	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	1843.80	kg	75.85	139852.23	INR One Lakh Thirty Nine Thousand Eight Hundred & Fifty Two and Paise Twenty Three Only
20	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	24.00	kg	77.95	1870.80	INR One Thousand Eight Hundred & Seventy and Paise Eighty Only
21	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge. All kinds of soil	5565.00	cum	128.05	712598.25	INR Seven Lakh Twelve Thousand Five Hundred & Ninety Eight and Paise Twenty Five Only
22	Extra for every additional lift of 1.5 m or part thereof in excavation / banking excavated or stacked materials. All kinds of soil	5565.00	cum	73.80	410697.00	INR Four Lakh Ten Thousand Six Hundred & Ninety Seven Only
23	CARRIAGE OF MATERIALS By Mechanical Transport including loading,unloading and stacking Earth Lead - 5 km	5565.00	cum	210.10	1169206.50	INR Eleven Lakh Sixty Nine Thousand Two Hundred & Six and Paise Fifty Only
24	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					5022700.31	INR Fifty Lakh Twenty Two Thousand Seven Hundred and Paise Thirty One Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				