

**Percentage BoQ**

Tender Inviting Authority: Staff Officer(Civil), Amrapali-Chandragupta Area

Name of Work:- Providing and Fixing of 6 nos of Hand pump in Different villages of Koyad Panchayat under GM Unit A-C Area,CCL (e-NIT No: 91 of 2024-25).

	<b>Category of Services (To Be Selected by Department)</b>	<b>Category of Bidder( To Be Selected by Bidder)</b>	<b>To Be Entered by Department</b>		
<b>ITC Not Available</b>	<b>Works Contract</b>	<b>Bidder's Status (Mandatory)</b>	<b>Rate of GST (in %)</b>	<b>GST to be Paid By Bidder (in Rs.)</b>	<b>GST to be Paid By CIL/Subsidiary (in Rs.)</b>
<b>Name of the Bidder/ Bidding Firm / Company :</b>		<b>Select</b>	<b>18.00</b>	<b>0.00</b>	<b>0.00</b>

**PRICE SCHEDULE**

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	<b>Part-A-</b> Drilling tube well for drilling in all kind of soil and rock for installation of hand pump with D.I rings all complete including supplying all materials, labours, tools, drilling, rigs, air compressor and equipments as well as fuel lubricant, for making 115/125mm dia boring etc. and cost of transporting rig machine and other vehicle up to site of work including contractor profit & O.H Charges as per specification and direction of Engineer Incharge. <b>Drilling upto 30 mtr depth below G.L in Rural area.</b>	180.00	meter	425.00	<b>76500.00</b>	INR Seventy Six Thousand Five Hundred Only
2	Drilling tube well for drilling in all kind of soil and rock for installation of hand pump with D.I rings all complete including supplying all materials, labours, tools, drilling, rigs, air compressor and equipments as well as fuel lubricant, for making 115/125mm dia boring etc. and cost of transporting rig machine and other vehicle up to site of work including contractor profit & O.H Charges as per specification and direction of Engineer Incharge. <b>Drilling beyond 31 mtr upto 60 mtr below G.L in Rural area.</b>	180.00	meter	458.00	<b>82440.00</b>	INR Eighty Two Thousand Four Hundred & Forty Only
3	Supplying of all tools, tackles & lowering of 125 mm PVC well casing pipe conforming IS:12818 all complete as per direction of EIC	180.00	meter	506.00	<b>91080.00</b>	INR Ninety One Thousand & Eighty Only
4	Providing and Fixing of ISI marked PVC plumbing pipe 32 mm dia all complete.	240.00	meter	175.95	<b>42228.00</b>	INR Forty Two Thousand Two Hundred & Twenty Eight Only
5	Providing and Fixing of ISI Mark deep Well hand pump for Indian Make MARK-II ISI 15500(PART 2)/2004 With Latest Revision including 12 mm x 3 Metre long 8 nos. connecting rods made of Bright bar electro-Galvanised fitted with coupler and normal stand assembly recommended for use with cylinder assembly suitable for borewell dia 100 to 125 mm Casing Pipe with all fitting complete as per direction of EIC.	6.00	Each	9600.00	<b>57600.00</b>	INR Fifty Seven Thousand Six Hundred Only
6	<b>PART-B</b> - Earthwork in excavation by mechanical means (Hydraulic excavator)/manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	3.14	Cum	188.45	<b>591.73</b>	INR Five Hundred & Ninety One and Paise Seventy Three Only
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement:4 coarse sand (zone-III) derived from natural sources:8 graded stone aggregate 40 mm nominal size derived from natural sources)	2.12	cum	5167.75	<b>10955.63</b>	INR Ten Thousand Nine Hundred & Fifty Five and Paise Sixty Three Only
8	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in cement mortar 1:4 (1 cement : 4 coarse sand)	6.67	sqm	673.45	<b>4491.91</b>	INR Four Thousand Four Hundred & Ninety One and Paise Ninety One Only
9	Dry brick pitching half brick thick in drains including supply of brick sand preparing the surface complete : With common burnt clay F.P.S. (non modular) bricks of class designation 5.0	15.26	sqm	504.55	<b>7699.43</b>	INR Seven Thousand Six Hundred & Ninety Nine and Paise Forty Three Only
10	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand:4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate 40 mm thick with 20 mm nominal size stone aggregate	15.26	sqm	452.50	<b>6905.15</b>	INR Six Thousand Nine Hundred & Five and Paise Fifteen Only
11	12 mm cement plaster of mix 1:4 (1 cement: 4 fine sand)	21.97	sqm	284.75	<b>6255.96</b>	INR Six Thousand Two Hundred & Fifty Five and Paise Ninety Six Only
12	Constructing soak pit 1.20x1.20x1.70m filled with brick bats including S.W. drain pipe 100mm diameter and 1.20 m long complete as per standard design.	6.00	no	2366.00	<b>14196.00</b>	INR Fourteen Thousand One Hundred & Ninety Six Only

13	Providing and Fixing of GI Socket Plain of 32 mm dia for Connection of Pipe as per instruction of EIC.	72.00	NO	43.25	<b>3114.00</b>	INR Three Thousand One Hundred & Fourteen Only
14	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos	<b>0.00</b>	<b>0.00</b>	INR Zero Only
<b>Total in Figures</b>					<b>404057.82</b>	INR Four Lakh Four Thousand & Fifty Seven and Paise Eighty Two Only
<b>Quoted Rate in Figures</b>			<b>Select</b>		<b>0.00</b>	INR Zero Only
<b>Quoted Rate in Words</b>					<b>INR Zero Only</b>	