

Tender Inviting Authority: Project Engineer(EnM),SDOCM							
Name of the Work / Contract No:		Repairing of Coal receiving plate of mainframe hopper between unloading point to conveyor chain carriage plate of BWF Make feeder breaker installed at Tarmi siding in R/O SDOCM Project			NIT No. : SDOCM/PE(EnM)e.Tender/24-25/35 dt.21.03.2025		
Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected)	To Be Entered by Department				
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
		Select	18	0.00	0.00	0.00	
Name of the Bidder/ Bidding Firm / Company :							
PRICE SCHEDULE							
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder In Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.01	Infrastructure making for repairing of coal receiving hopper. a) M.S channel (100x50) mm cutting work.16"x06 Nos b) M.S plate (3.16mm) cutting work for above.(40"x60") x 02 side c) Welding work for above work(96"x80"+96")	1	Inch			0.00	INR Zero Only
1.02	Cutting of R.S joist (200x100) mm and M.S channel (100x50) mm changing of structure of above coal receiving hopper. a) Old & damaged structure member cutting work. 24"x08 Nos 36"x02 side x 08 Nos b)New steel materials cutting work. 32"x04 Nos (R.s.joist cutting) 36"x04 Nos. (T. making) c) Above steel materials fixing and fitting with proper levelling then Multilayer welding work. (i) 32"x08 x Nos x 03 layer (ii) 36"x08 x Nos x 02 side 03 layer (d) M.s channel(100x50) mm cutting for inserting as strengthening Purpose (i) 16"x08 Nos (e) Welding work for above channel (100x50) mm. (i) 16"x08 Nos 03 layer (ii) 36"x02 side x 08 Nos x 02 layer	1	Job			0.00	INR Zero Only
1.03	M.S plate (16mm) cutting work for coal receiving mother plate (i) (105"+76") x 02 side x 03 Nos. (99"+35") x 02 side. (ii)	1354	Inch			0.00	INR Zero Only
1.04	Damaged & tear-bear mother plate of coal receiving hopper work. (i) (36"+24") x 02 side x 02 times x 02 Nos. (ii) (28"+24") x 02 side 02 times x 03 Nos.	1104	Inch			0.00	INR Zero Only
1.05	All scrap materials removing from working site , coal dust, cleaning new steel materials shifting at working site placing by chain block fitting and fitting with the help of 'L' & 'V' wedges by hammering method with proper levelling etc. (i) 02 fitter x 02 shift x 03 days (ii)10 helper x 02 shift 03 days	1	Job			0.00	INR Zero Only
1.06	After fixing and fitting multilayer welding work for above work. (i) (105"+76") x 02 side x 03 Nos x 03 layer. (ii) (96"+35") x 02 side x 04 layer.	4330	Inch			0.00	INR Zero Only
1.07	After work completion cutting of infrastructure for removing purpose.	272	Inch			0.00	INR Zero Only
1.08	Add contractor profit	1	Job			0.00	INR Zero Only
1.09	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	Zero Only
Quoted Rate in Words		INR Zero Only					