

Tender Inviting Authority: Staff officer (E&M), Magadh - Sanghmitra Area, CCL						
Name of the Work / Contract No:	Work of " Providing Main control Switch and cable & Fixing of lighting arrangement in Pratiksha Parisar under Magadh Sanghmitra Area.".			NIT No: G.M.(M-S)/S.O.(E&M)/e-NIT/24-25/91; Dated:- 18.03.2025.		
Category of Services (To Be Selected by Department)			Category of Bidder (To Be Selected by Bidder)			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Providing and fixing following rating and breaking capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required.400 A, 50 KA,FPMCCB	1	Each		0.00	INR Zero Only
2	Supply and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheated / XLPE aluminium conductor cable of 1.1 kv grade as required. 4X35 sq. Mm (32mm)	50	Mtr		0.00	INR Zero Only
3	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board , 415 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/isolator) 8 way (4 + 24), Double door	1	Each		0.00	INR Zero Only
4	Supply and fixing of 32 mm dia X 2.00 metres long G.I. Pipe (Medium class) bracket for mounting of fluorescent / HPMV/HPSV street light fitting on pole including bending the pipe to the required shape, 2 nos 40 mm X 3 mm flat iron clamps with nuts, bolts and washer, painting the flat iron with primer and finish paint etc. as required.	25	Each		0.00	INR Zero Only
5	Supplying and drwing of 2x6 sq mm of FR PVC insulated copper conductor single core in the existing surface recessed steel/ PVC conduit as required.	198	Mtr		0.00	INR Zero Only
6	Supplying and fixing following rating, double pole, (Single phase and neutral), 240 V, residual current circuit breaker (RCCB), having a sensitivity Current 30 MA in the existing MCB DB completer with connections, testing and commissioning etc. As required 40 A	4	Each		0.00	INR Zero Only
7	Wiring for circuit / submain wiring alongwith earth wire with the following sizes of FRLS PVC insluated copper conductor, single core cable in surface/ recessed steel conduit as required 2 X 1.5 sq mm + 1 x 1.5 sq. Mm earth wire.	156	Mtr		0.00	INR Zero Only
8	Total impact of GST for the purpose of CTC	1.000	Job	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only	