

Estimate for the work- "Facelifting of Temples on occasion of Ramnavmi under Bhurkunda Project, Barka Sayal Area."

S. No.	Description	Qty	Unit	Rate	Amount	CPWD SOR-24
1	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour Two coats	2080.67	sqm	89.25	₹ 185,699.80	13.83.2
2	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :One or more coats on old work	321.19	sqm	65.65	₹ 21,086.25	13.99.1
3	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	83.23	sqm	98.45	₹ 8,193.99	13.80
4	Colour washing such as green, blue or buff to give an even shade :New work (two or more coats) with a base coat of white washing with lime	508.00	sqm	33.4	₹ 16,967.20	13.39.1

₹ 231,947.24

Add GST @18%

₹ 41,750.50

Total Amount

₹ 273,697.74

This is certified that:-

- This work has not been executed in advance without any proper work order.
- No spiltting of work has been done in this proposal and it is a complete proposal as per requirement.