

Item Rate BoQ

Tender Inviting Authority: Staff officer(E&M), Piparwar Area						
Name of the Work / Contract No:	Revival /repairing /replacement of garden light of D type Qtr. No. D-01 to D-08, D-10, D-13 and D-16 at Sangam Vihar colony under G.M. unit, Piparwar Area.				NIT No. : SO(E&M)/PPR/e-NIT/24-25/73	
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)		Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate (Without Taxes) in Rs. P	BASIC RATE (Without Taxes) In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation and refilling the trench etc as required, but excluding sand cushioning and protective covering. Upto 35 sq. mm.	460	Meter	135.00		0.00	INR Zero Only
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources). (0.35 m X 0.35 m X 0.35 m X 80 Nos. = 3.43 Cum).	3.43	Cum	6490.90		0.00	INR Zero Only
3	Supplying and fixing 25 Amps rating, double pole, (single phase and neutral), 240 V, residual current circuit breaker (RCCB),having a sensitivity current 30 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required	11	Each	1766.00		0.00	INR Zero Only
4	Supplying and drawing 3 x 4 sq. mm FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.	85	Meter	177.00		0.00	INR Zero Only
5	Supplying and fixing metal box of 180 mm X 100 mm X 60 mm deep sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc. as required.	11	Each	197.00		0.00	INR Zero Only
6	Supplying and fixing of 50 mm sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.	88	Meter	237.00		0.00	INR Zero Only
7	Supply of 4 Sq.mm, 2 core copper armoured cable 1.1 KV grade. (Laying cost has been included in estimate Sl. No. 01).	445	Meter	254.24		0.00	INR Zero Only
8	Supplying and fixing of post top decorative cast aluminium rust resistance bollard type garden light 10 Watts.	83	Nos.	4628.53		0.00	INR Zero Only
9	Supplying and fixing of 2+2 way, SPN, single door, MCB DB.	84	Nos.	1015.74		0.00	INR Zero Only
10	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only						