

Validate

Print

Help

**Percentage BoQ**

Tender Inviting Authority:STAFF OFFICER CIVIL

Name of Work: Provision of garland drain, hume pipes and other misc. works for monsoon preparation 24-25 at JOCP, Hazaribagh Area

	<b>Category of Services (To Be Selected by Department)</b>	<b>Category of Bidder( To Be Selected by Bidder)</b>	<b>To Be Entered by Department</b>		
<b>ITC Available</b>	<b>Works Contract</b>	<b>Bidder's Status (Mandatory)</b>	<b>Rate of GST (in %)</b>	<b>GST to be Paid By Bidder (in Rs.)</b>	<b>GST to be Paid By CIL/Subsidiary (in Rs.)</b>
<b>Name of the Bidder/ Bidding Firm / Company :</b>		<b>Select</b>	<b>18.00</b>	<b>0.00</b>	<b>0.00</b>

**PRICE SCHEDULE**

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

<b>NUMBER #</b>	<b>TEXT #</b>	<b>NUMBER #</b>	<b>TEXT #</b>	<b>NUMBER</b>	<b>NUMBER #</b>	<b>TEXT #</b>
<b>Sl. No.</b>	<b>Item Description</b>	<b>Quantity</b>	<b>Units</b>	<b>Estimated Rate in Rs. P</b>	<b>TOTAL AMOUNT in Rs. P</b>	<b>TOTAL AMOUNT In Words</b>
<b>1</b>	<b>2</b>	<b>3</b>	<b>4</b>	<b>5</b>	<b>6</b>	<b>7</b>
1	<b>Item Description/ Heading</b>					
1.01	Earth work in excavation by excavator) / mechanical means (Hydraulic manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, 6484.80  including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	6484.80	Cum	188.45	<b>1222060.56</b>	INR Twelve Lakh Twenty Two Thousand &Sixty and Paise Fifty Six Only
1.02	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm removal of rubbish up to a distance of 50m outside the periphery of the area cleared	4800.00	Sqm	10.20	<b>48960.00</b>	INR Forty Eight Thousand Nine Hundred & Sixty Only
1.03	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	13.53	Cum	5322.15	<b>72008.69</b>	INR Seventy Two Thousand &Eight and Paise Sixty Nine Only
1.04	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4(1 cement: 4 fine sand)	193.00	Sqm	284.75	<b>54956.75</b>	INR Fifty Four Thousand Nine Hundred & Fifty Six and Paise Seventy Five Only
1.05	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement coarse sand : 6 graded stone aggregate 20 mm nominal size).	8.92	Cum	5916.00	<b>52770.72</b>	INR Fifty Two Thousand Seven Hundred & Seventy and Paise Seventy Two Only

1.06	Laying Reinforced Cement Concrete Pipe NP4/prestressed Concrete pipe on first class bedding in single row . (Laying Reinforced cement concrete pipe NP4/prestressed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets.) 1200mm diameter	30.00	Metre	8557.00	256710.00	INR Two Lakh Fifty Six Thousand Seven Hundred & Ten Only
1.07	Supplying and stacking at site. .Supplying and stacking at site. Moorum	26.50	Cum	771.15	20435.48	INR Twenty Thousand Four Hundred & Thirty Five and Paise Forty Seven Only
1.08	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length total length 90 m) having 50 no rounds per 6 metre length, upto 3m height of wall with existing angle iron Y shaped placed 2.4m or 3.00m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape (R.B.T.) /Spring core (2.5mm thick) wire of high tensile strength of 165 kg sq.mm with tape (0.52 mm thick) and weight 43.478gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	180.00	Metre	255.85	46053.00	INR Forty Six Thousand & Fifty Three Only
1.09	Structural steel work in single section fixed with or without connecting plate including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	168.00	Kg	77.95	13095.60	INR Thirteen Thousand & Ninety Five and Paise Sixty Only
1.10	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift upto 1.5 m. All kinds of soil	250.00	Sqm	19.75	4937.50	INR Four Thousand Nine Hundred & Thirty Seven and Paise Fifty Only
2.00	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos	<b>0.00</b>	<b>0.00</b>	INR Zero Only
<b>Total in Figures</b>					<b>1791988.29</b>	INR Seventeen Lakh Ninety One Thousand Nine Hundred & Eighty Eight and Paise Twenty Nine Only
<b>Quoted Rate in Figures</b>			<b>Select</b>		<b>0.00</b>	INR Zero Only
<b>Quoted Rate in Words</b>	<b>INR Zero Only</b>					