

Tender Inviting Authority: SOE&M, GM Unit Kuju							
Name of the Work / Contract No:	Providing Uninterrupted power supply to CCTVs surveillance system installed at Coke stock and crusher point location by using Aerial Bunch cable 70 sqmm 4 core from 200KVA DG SET installed at karma project under kuju Area.				NIT No. : GM (K)/EnM/e-Tender/24-25/295		
Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department				
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00	
PRICE SCHEDULE							
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
2	Supply of Cement RCC Pole 11-12 Meter	11.00	nos			0.00	INR Zero Only
3	Erection of RCC/PCC pole of following length in brick ballast and ramming the foundation, finishing with 150mm thick cement concrete (1.3.6) layer on top with including excavation and refilling etc as required	11.00	nos			0.00	INR Zero Only
4	Supply of two lengths of channel iron 75 mmX40 MMX5 7 Kg/m double pole cross arm for 3 wire O.H. kline conductors complete with through bolts & nuts for clamping to the poles 50 mm X 6 mm MS flats welded on one side th the channel iron and with bolts & nuts on the other side for lying cross arm together, including drilling holes for insulators Pins/fitings, nols & nuts etc and painting with primer and finish paint as required.	5.00	nos			0.00	INR Zero Only
5	Supply and fixing of Aerial bunch 70 Sq mm 4 core Cable	700.00	mtr			0.00	INR Zero Only
6	Supply and fixing of AB Cable Dead end clamp	8.00	nos			0.00	INR Zero Only
7	Supply and fixing of AB Cable Suspension clamp	20.00	nos			0.00	INR Zero Only
8	Supply and fixing of piercing connector for AB	44.00	nos			0.00	INR Zero Only
9	Supply and fixing of Single door AB cable SMC distribution box	5.00	nos			0.00	INR Zero Only
10	Supplying and erection of bow stay set complete (galvanised) with 19/20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, turn buckle (20 mm X 60 cm), 7/4.00 mm dia G.I stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement 3 coarse sand 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling and also with 0.6 m long brace of size 50 mm X 50 mm X 6 mm angle iron with 50 mm dia pulley fixed at one end of the brace as required	5.00	nos			0.00	INR Zero Only
11	Providing and fixing following rating and breaking capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required. 630 A,50KA,FPMCCB	1.00	nos			0.00	INR Zero Only
12	LOADING AND UNLOADING OF POLES	20.00	nos			0.00	INR Zero Only
13	Supply and installation of 12 KW timer switch with 24 Hrs. Digital timer 65 A rated contactor and 63 A rated SPN.	1.00	nos			0.00	INR Zero Only
14	Total impact of GST for the purpose of CTC	1.000 nos				0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words							INR Zero Only