Print Help

Item Rate BoQ

Tender Inviting Authority : Staff Officer (Civil), Magadh-Sanghmitra Area.

| Name of the Work / Contract No: | Providing and Laying of hume pipes under Magadh OCI | P of Magadh-Sa | nghmitra Area. (e NIT No. 07 of | 2025-26) | | | |
|--|--|----------------|---|--|----------------------------|-------------------------------------|---|
| | Category of Services (To Be Selected by Department) | | Category of Bidder (To Be Selected by Bidder) | To Be Entered by Department | | | |
| TC Available | Works Contract | | Bidder's Status (Mandatory) | Rate of GST (in %) | Total GST(in Rs.) | GST to be Paid By Bidder (in Rs.) | GST to be Paid By CIL/Subsidiary (in Rs.) |
| Name of the Bidder/ Bidding Firm / Company : | | | Select | 18 | 0.00 | 0.00 | 0. |
| (This BOQ ten | nplate must not be modified/replaced by the bidder and t | the same shoul | | RICE SCHEDULE event columns, else the bidder is l | iable to be rejected for t | his tender. Bidders are allowed to | o enter the Bidder Name and Values only) |
| NUMBER # | TEXT # | NUMBER # | TEXT # | NUMBER | NUMBER # | NUMBER # | TEXT # |
| SI. No. | Item Description | Quantity | Units | Estimated Rate in Rs. P | Figures To be entered | TOTAL AMOUNT Without Taxes in Rs. P | TOTAL AMOUNT In Words |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| 1 | Excavation in Soil using Hydraulic Excavator CK 90 and Tippers with Disposal upto 1000 metres. Excavation for roadwork in soil with hydraulic excavator of 0.9 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to the embankment location within all lifts and lead upto 1000m (excluding Royalty @ Rs. 24.00 per Cum but excluding watering, rolling & compaction) | 1871.25 | Cum | | | 0.00 | INR Zero Only |
| 2 | Laying Reinforced Cement Concrete Pipe NP4/prestrssed concrete pipe on first class bedding in single row. (Laying Reinforced cement concrete pipe NP4/prestrssed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets.): 1000 mm dia | 50.00 | Mtr | | | 0.00 | INR Zero Only |
| 3 | Laying Reinforced Cement Concrete Pipe NP4/prestrssed concrete pipe on first class bedding in single row. (Laying Reinforced cement concrete pipe NP4/prestrssed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets. § 1200 mm dia | 150.00 | Mtr | | | 0.00 | INR Zero Only |
| 4 | Embankment Construction with Material Obtained from Borrow Pits (Construction of embankment with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement of table 300-2): Rolling with vibratory roller | 517.92 | Cum | | | 0.00 | INR Zero Only |
| 5 | Total impact of GST for the purpose of CTC | 1.000 | Nos | | 0.00 | 0.00 | INR Zero Only |
| Total in Figures | | | <u> </u> | <u> </u> | | 0.00 | INR Zero Only |
| Quoted Rate in Words | | | | | INR Zero Only | | |