| | Va | | |
|--|----|--|---|
| | | | |
| | | | |
| | | | • |

Print Help

Item Rate BoQ

Tender Inviting Authority: Project Engineer (E&M), Tetariakhar OCP

Name of the Work / Maintenance and Erection & Dismantling of 440/220 Volt Lighting Overhead (OH) Line Before Monsoon for Proper Maintenance of Critical Location LT Overhead Lines under Tetariakhar OCP, Rajhara Area.

| Name of the Work / Contract No: | Maintenance and Erection & Dismantling of 440/220 Volt Lighting Overhead (OH) Line Before Monsoon for Proper Maintenance of Critical Location LT Overhead Lines under Tetariakhar OCP, Rajhara Area. | | | | | | | | | |
|--|--|---|-----------------------------|----------------------------|--|--------------------------------------|---|--|--|--|
| | Category of Services (To Be Selected by Department) | Category of Bidder (To Be Selected by Bidder) | To Be Entered by Department | | | | | | | |
| ITC Available | Works Contract | | Bidder's Status (Mandatory) | Rate of GST (in %) | Total GST(in Rs.) | GST to be Paid By Bidder (in Rs.) | GST to be Paid By CIL/Subsidiary (in Rs.) | | | |
| Name of the Bidder/ Bidding Firm / Company : | | | Select | 18 | 0.00 | 0.00 | 0.00 | | | |
| | (This BOQ template must not be modified/replaced by the bidder and the sam | e should be uploa | PRICE SCHE | | ed for this tender. Bidders | are allowed to enter the Bidder Name | and Values only) | | | |
| NUMBER # | TEXT # | NUMBER# | TEXT # | NUMBER | NUMBER# | NUMBER # | TEXT# | | | |
| SI. No. | Item Description | Quantity | Units | Estimated Rate in Rs. P | BASIC RATE In Figures To be entered by the Bidder in Rs. P | TOTAL AMOUNT Without Taxes in Rs. P | TOTAL AMOUNT In Words | | | |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | | | |
| 1 | Erection of metallic pole of following length in cement concrete 1:3:s (1 cement ;3 coarse sand ;6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling et ca s required .above 8 metre and upto 11 metre . | 10 | Nos. | | | 0.00 | INR Zero Only | | | |
| 2 | Supplying and erection of stay set complete (galvanised) with 19/20 mm x 1.8 metres long stay rod, anchor plate of size 45cm x 45cm x 7.5mm, thimble, stay clamps, bow tightener,7/4 mm dia G. 1 stay wire and strain insulator etc in cement concrete 1:3:6 [1 cement : 3 coarse sand:6 grade stine aggregate 40 mm nominal size) foundation including excavation and refiling etc. | 10 | Nos. | | | 0.00 | INR Zero Only | | | |
| 3 | Supplying of channel iron 75 mm x 40 mm x6 mm (7.14 kg per metre) cross arm for 4 wire over head line complete with clamps, bolts, nuts and washer etc including of holes for insulator point bolts, nuts and washers etc (as per drawing) and painting with primer and finish paints as required | 10 | Nos. | | | 0.00 | INR Zero Only | | | |
| 4 | Erection of all aluminium conductor of 7/3.40mm to 7/4.00 mm diameter and above including binding etcas required 60span x4wire x including binding etca s required | 150 | Kg | | | 0.00 | INR Zero Only | | | |
| 5 | Erection of angle iron /channel iron cross arm on wood /rcc/pcc/steel tubular /rail pole etc as required. | 10 | Set | | | 0.00 | INR Zero Only | | | |
| 6 | Erection of cradle guard as required. | 25 | Each | | | 0.00 | INR Zero Only | | | |
| 7 | Supply & Erection of pin insulator. 440 v | 48 | Set | | | 0.00 | INR Zero Only | | | |
| 8 | Erection of G.I wire no.8 SWG including binding etc .as required for earth continuity. | 90 | Kg | | | 0.00 | INR Zero Only | | | |
| 9 | Supply & Erection of shackle insulator of size 100mm x1110mm with GI bolt, And straps etc .as required. | 40 | Set | | | 0.00 | INR Zero Only | | | |
| 10 | Dismantling of pole/street light standard /strut embedded in cement concrete foundation etc.as required | 7 | Each | | | 0.00 | INR Zero Only | | | |
| 11 | Dismantling of over head lines comprising of copper/alluminium over head conductor G.I wire cross arms ,insulators etc.as required | 90 | Кg | | | 0.00 | INR Zero Only | | | |
| 12 | Total impact of GST for the purpose of CTC | 1 | Nos | | 0.00 | 0.00 | INR Zero Only | | | |
| Total in Figures | | | | | | 0.00 | INR Zero Only | | | |
| Quoted Rate in Words | INR Zero Only | | | | | | | | | |