

Tender Inviting Authority: Staff officer (E&M), Magadh - Sanghmitra Area, CCL						
Name of the Work / Contract No:	Work of " Provision of surge protection device at rail in motion weighbridges of Balumath, Phulbasiya Railway siding, and Road weighbridge number 13, 17, 18, 19, 20, 21, 22 & 23 for protection of electronic instruments from surge and spikes during rainy season under Magadh OCP, M-S Area..".			NIT No: G.M.(M-S)/S.O.(E&M)/e-NIT/25-26/01; Dated:- 05.04.2025.		
Category of Services (To Be Selected by Department)			Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Surge Protection device (SPD) 230 Volt, Single phase, Class-1, Class 1 + Class II Combination: Voltage switching and voltage limiting, IP20	11	No.		0.00	INR Zero Only
2	Providing for fixing of 25 sqmm single core flexible copper cable earth pit to SPD ((11 X 15 Mtr)*5% wastage)	173	Mtr		0.00	INR Zero Only
3	Supplying and fixing 5 amps to 32 amps rating, 240/415volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc as required. Single pole & neutral.	11	No.		0.00	INR Zero Only
4	Supplying and fixing Cable End Box (Loose Wire Box) suitable for following single pole and neutral, sheet steel, MCB distribution board, 240Volts,on surface/ recess, complete with testing and commissioning etc.as required.	11	No.		0.00	INR Zero Only
5	Earthing with copper earth plate 600 mmX600mm X 3 mm thick including accessories and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 mtr. Long etc.with charcoal/coke and salt as required	11	No.		0.00	INR Zero Only
6	Providing and fixing earth bus of 50 mm X 5 mm copper strip on surface for connections etc. as required (0.5*11)*5% wastage)=5.775 mtr	5.775	Mtr		0.00	INR Zero Only
7	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/recessed medium class PVC conduit as required 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire((11*2)*5% wastage)=23.1 mtr	23.1	Mtr		0.00	INR Zero Only
8	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required, 32mm (Earth bus to earthpit)((11X 15 Mtr)*5% wastage)	173	Mtr		0.00	INR Zero Only
9	Supplying and fixing Cable End Box (Loose Wire Box) suitable for triple pole and neutral, sheet steel, Vertical MCB distribution board, 415 Volts, on surface/ recess, complete with testing and commissioning etc. as required.	11	No.		0.00	INR Zero Only
10	Providing and fixing 4.00 mm dia copper wire on surface or in recess for vloop earthing as required. ((11 X 15 Mtr)*5% wastage)	173	Mtr		0.00	INR Zero Only
11	Fixing charge of supplied item at 15% of item cost from serial number 1 and 2	1	Job		0.00	INR Zero Only
12	Total impact of GST for the purpose of CTC	1.000	Job	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				